

M.J. BRADLEY & ASSOCIATES

1000 Elm Street.
Second Floor
Manchester, NH 03101
Tel: 603-647-5746
Fax: 603-647-0929

47 Junction Square Drive
Concord, MA 01742
Tel: 978-369-5533
Fax: 978-369-7712

DOCUMENT TRANSMITTAL SHEET

TO: STEVE RAPP

FROM: STEVE PIPER

COMPANY: EPA REGION 1

DATE: 8-26-10

RE: CHELSEA TERMINAL ODOR CONTROL

NOTES/COMMENTS:

As a follow up to our recent telephone conversation, I am enclosing a copy of the air permit application submitted to the Massachusetts DEP to gain approval for the Chelsea Terminal odor control system to be upgraded to a RTO control device in order to also serve as a VOC control device for the residual oil storage tank and residual oil truck loading operations. I am hopeful that the information contained within the application will answer many of your questions.

Don't hesitate to call me with an additional questions or data request 603-647-5746 ext 102.

**NON-MAJOR CPA APPLICATION FOR EMISSION
CONTROL SYSTEM
TRANSMITTAL NO. W213528**

**CHELSEA SANDWICH LLC
11 BROADWAY
CHELSEA, MASSACHUSETTS**

Prepared for

Chelsea Sandwich LLC
11 Broadway
Chelsea, MA 02150

April 11, 2008

Prepared by

M.J. Bradley & Associates
1000 Elm Street, Second Floor
Manchester, NH 03101

CONTENTS

1	INTRODUCTION	1-1
2	PROJECT, EQUIPMENT AND EMISSIONS DESCRIPTION	2-1
2.1	Facility Emissions Information	2-1
2.2	Proposed Emission Control Device	2-2
2.3	Proposed Emission Capture System	2-2
2.4	Proposed Operating Limits	2-3
2.5	Property Line Noise Impact	2-4
3	FIGURES/ILLUSTRATIONS	3-1
4	APPLICATION FORMS	4-1
5	BEST AVAILABLE CONTROL TECHNOLOGY ANALYSIS	5-1
6	RECORDKEEPING AND REPORTING PROCEDURES	6-1
6.1	Combustion Emissions	6-1

APPENDIX A EMISSION CALCULATIONS

APPENDIX B STANDARD MAINTENANCE AND OPERATING PROCEDURES

APPENDIX C MANUFACTURER SPECIFICATIONS

APPENDIX D NOISE IMPACT CALCULATIONS

1 INTRODUCTION

On behalf of Chelsea Sandwich LLC, an affiliate of Global Companies LLC, M.J. Bradley & Associates (MJB&A) submits to the Massachusetts Department of Environmental Protection (DEP), Northeast Regional Office (NERO), a Non-Major Comprehensive Plan Approval (CPA) Air Quality Permit application. This application package includes proposed emission limitations and information for an emission control system to be installed at the Chelsea Sandwich facility located at 11 Broadway, Chelsea, Massachusetts (Facility). The Facility previously installed a dry scrubbing odor control system designed to control total reduced sulfurs (TRS) per agreement with the City of Chelsea in response to odor complaints. While the system was effective at reducing odors, during routine environmental compliance monitoring and testing it was determined that the treatment bed life was much shorter than expected. Follow-up investigatory testing of the odor control system exhaust stream (collected from the residual oil storage tanks and residual oil loading rack lanes) revealed higher than expected VOC levels as opposed to those previously calculated using EPA-published emission factors. Because the higher VOC levels compromised the treatment bed life of the dry scrubbing odor control system and revealed the potential for Terminal VOC emissions to exceed the major source threshold, Chelsea Sandwich LLC is voluntarily proposing to install a Regenerative Thermal Oxidizer (RTO) as a means to effectively reduce odors and VOC emissions to sustain the current minor source status.

This document includes applicable BWP AQ 02, BWP AQ CPA-3, and BWP AQ SFP-5 application forms and supporting information, including the following:

- Project, Equipment and Emissions Descriptions Section 2
- Figures/Illustrations Section 3
- Application Forms Section 4
- BACT Determination Section 5
- Recordkeeping and Reporting Section 6

2 PROJECT, EQUIPMENT AND EMISSIONS DESCRIPTION

The Chelsea Sandwich LLC facility, located at 11 Broadway in Chelsea, is essentially under the Tobin Bridge as illustrated in the Figure 3-1 topographical map. Figure 3-2 provides a site plan of the entire facility and identifies the location of the tanks, loading rack and emission control device that are the subject of this application.

This facility handles distillate and residual oil products. The facility operates under the standard industrial classification (SIC) code 5171, Petroleum Bulk stations and Terminals and receives petroleum products by ship or barge into onsite storage tanks and then loads over-the-highway trucks and barges from their storage tanks. Emissions at the facility occur as results of vapors displaced during filling of tanks and trucks and storage tank “breathing”.

In an effort to address odor complaints from nearby residents in Chelsea, on May 6, 2005, it was agreed with the Chelsea Board of Health that a system would be installed at the Facility to control these odors. Because the petroleum odors are generally considered to be a result of Total Reduced Sulfurs (TRS), the emission capture system was designed to collect emissions from the residual oil storage tanks and the residual oil truck loading. The emission control system was designed to reduce TRS using a dry scrubbing media and did not require pre-approval permitting from the DEP.

Although the control device was effective at reducing odors, it was determined through the facilities routine compliance monitoring that the bed life was found to be shorter than expected. In response to the issues identified during the compliance monitoring and in accordance with established protocol, testing was conducted on the emission control inlet to evaluate the emission characteristics as a means to determine what was causing the bed to “breakthrough” in such a short period. Results of the testing revealed much higher than expected total VOC emissions.

The following sections provide information about the emission characteristics and the proposed new strategy for controlling odors and VOC emissions.

2.1 Facility Emissions Information

Chelsea Sandwich LLC is requesting emission and throughput limitations as a means to continue to be categorized as a minor source. Historically the Facility was categorized as a natural minor source of air pollution with VOC emissions less than 50 tpy at maximum potential throughputs, as calculated using EPA-published emission factors (AP-42 and TANKS models). After testing the inlet to the odor control system (includes exhaust from residual oil storage tanks and residual truck loading) it appeared that potential uncontrolled VOC emissions could exceed 50 tpy. The

newly calculated facility-wide potential VOC emissions with the proposed 95% capture of residual oil tank emissions, 90% capture efficiency of the residual oil truck loading emissions and 99% destruction efficiency of captured emissions from both is shown in the table below. The facility-wide emissions of other criteria pollutants represent byproducts of combustion based on AP-42 emission factors for the Facility boilers and the RTO (except for NO_x and CO from the RTO, which are based on vendor guarantees of 3 ppm NO_x and 50 ppm CO).

Pollutant	Potential Emissions (tpy)
VOC	37.1
NO_x	36.0
SO_x	50.3
CO	11.8
PM	5.0
Total HAPs	5.6

Supporting calculations can be found in Appendix A.

2.2 Proposed Emission Control Device

Chelsea-Sandwich LLC is proposing to install a 9,000 scfm regenerative thermal oxidizer (RTO) to destruct the VOC and TRS emissions from the evaporative losses associated with the residual oil storage tanks and the residual oil truck loading operations. A diagram of the unit is provided in Figure 3-3. The vendor performance guarantee for the RTO is 99% destruction efficiency of VOC and TRS operating at a minimum chamber temperature of 1,500 F (design residence time is 1.0 seconds). Vendor specifications are provided in Supplemental Form BWP AQ SFC-5 and with backup information attached in Appendix C.

2.3 Proposed Emission Capture System

Emissions captured for control by the proposed RTO include those from the residual oil storage tanks and the residual oil truck loading. These sources contain the majority of TRS, which make them the target of the odor control strategy. The following describe the emission collection system for the two source types.

Tank Vents

The capture system for the residual oil storage tanks is a "T" arrangement illustrated in Figure 3-4 that maintains a constant draw of up to 850 cfm. The basis for the design flow rate is to handle the displaced air from the tank headspace during a filling operation that has a maximum pump rate of 9,000 barrels/hour. During times when the tank is not filling, the capture system will maintain a constant exhaust rate in order to capture vapor displacement associated with other

operations, such as tank-to-tank transfers, air sparging and any breathing emissions associated with the residual oil tanks. By design of the T arrangement, any portion of the exhaust rate that is not from the tank displacement will come from intake of fresh air. The purpose of the T design is to assure that the tank is always stabilized to atmospheric pressure in order to meet petroleum tank safety requirements that assure tanks do not distort due to overpressure or collapse due to vacuum. The capture efficiency rating by the design engineer is minimally 95%.

Truck Loading

The capture system for the residual oil truck loading is a flex hose arrangement illustrated in Figure 3-5 that maintains a constant draw of up to 300 cfm from each loading lane. The use of flex hose is necessitated to enable effective use for the different truck configuration that may load at the rack. Additionally, the residual loading is accomplished by a top-loading arm that goes down into the truck hatch. The flex hose is positioned by the operator beside the loading arm. The flex hose cannot have a tight connection, as it is necessary for the operator to view the oil level in the truck to eliminate any risk of overflow spillage. Because the truck has varying diameter hatches the capture efficiency rating by the design engineer is 90%.

2.4 Proposed Operating Limits

Chelsea-Sandwich LLC proposes to implement the following:

- a) Potential VOC emissions associated with residual storage tanks are calculated assuming the maximum anticipated inlet concentration of 2,000 ppm (based on 4,300 scfm) and a 95% capture efficiency and a 99% control efficiency of the captured emissions. Based on this calculation the maximum RTO outlet concentration would be 20 ppm or 0.63 lb/hr (based on 4,300 scfm). While the RTO capacity is 9,000 scfm, the actual flow will be a function of efforts to optimize and calibrate the individual capture hoods. We expect the VOC pounds per hour to be relatively constants regardless of the flow.
- b) Potential VOC emissions associated with residual oil truck loading will be calculated assuming the maximum anticipated inlet concentration of 2,000 ppm (based on 300 scfm per loading lane), a truck loading throughput limitation of 500,000,000 gallons per year of residual oil, and a 90% capture efficiency and a 99% control efficiency of the captured emissions.
- c) Potential VOC emissions for the distillate portion of the terminal will be calculated using AP-42 emission factors and the product throughput. Truck loading rack throughput limitations for the distillate products will be:
 - Kerosene – 15,000,000 gallons/year
 - No. 2 Oil – 438,000,000 gallons/year

d) Potential VOC emissions from barge loading operations were calculated using AP-42 emission factors for the distillate products and a revised emission factor for residual products. Based on the testing performed on the exhaust from the residual oil truck loading rack the emissions were determined to be 433 times the AP-42 emission factor, the Barge Loading emission factor of 0.00009 lb/1,000 gal was changed to 0.039 lb/1,000 gal. The following products limits were used for Barge Loading:

- Kerosene – 10,000,000 gallons/year
- Distillate Oil – 60,000,000 gallons/year
- Residual Oil – 60,000,000 gallons/year

2.5 Property Line Noise Impact

As requested by DEP during the pre-application meeting, a noise impact assessment was conducted. The specific concern of the DEP was the noise associated with the bed switching mechanisms. According to the RTO manufacturer (Adwest) there is no noise data for Model RETOX 9.0 RT095 related to the bed switching. However, Adwest did feel comfortable saying that the noise associated with bed switching was less than the noise of the fan. With that said, Adwest provided the following center frequency sound pressure levels based on hemispherical, free field radiation, with a directivity factor of 2 at a measurement of 5 feet. Values are dBA:

AVG	63 Hz	125 Hz	250 Hz	500 Hz	1kHz	2kHz	4 kHz	8kHz
90	105	108	104	94	85	79	75	73

The location of the Facility is considered urban and is adjacent to a major urban thoroughfare (Tobin Bridge). MJB&A has assumed a background urban sound pressure level, L_{90} , of 67 dBA for general ambient conditions between midnight and 2:00 a.m. for comparison to property line levels.


Appendix D presents the calculation to determine the nearest property line, based on site plans that were provided by Chelsea Terminal. The “source” is assumed to be the RTO. The ground-level property line is 20 feet from the RTO. (Refer to Attachment 3-2 for the Site Plan).

In summary, a dBA value of 58 was calculated at the property line based on the sound pressure decay over 20 foot and a minimal 20dB drop caused by the existence of a brick building located directly between the RTO and the property line. Using the same calculations for the additional distance to the nearest resident (50 ft), the noise level was calculated to be 50 dB. Both the fence line and nearest resident impacts were below the background level of 67dBA. In addition, examination of spectral data does not exhibit any pure tone conditions.

3 FIGURES/ILLUSTRATIONS


The following illustrations, as required by the CPA application, have been included in this section:

- Topographic Site Map Figure 3-1
- Site Plan Figure 3-2
- Tank & Truck Capture Systems Figures 3-3 and 3-4
- RTO Diagram Figures 3-5, 3-6, 3-7 and 3-8




UTM 19 331662E 4694549N (NAD27)
Polonia Playground, USGS Boston North (MA) Quadrangle
 Projection is UTM Zone 19 NAD83 Datum

$$\begin{aligned} M &= -15.281 \\ G &= -1.379 \end{aligned}$$



RECEIVED
JUL 17 10 58 AM '01
INSPECTIONAL
SERVICES



LEGEND

- 1 FOAM HOUSE, FIRE PROTECTION EQUIPMENT
- 2 2 1/2\" foam hydrant (hole station) 600-5 nozzle
- 3 4-2 1/2\" fire dept. pumper hose connections
- 4 2 1/2\" water hydrant
- 5 2 1/2\" foam hydrant
- 6 FIRE ALARM PULL BOX
- 7 FOAM VALVES IN SUB-SURFACE PIT
- Q YARD WATER HYDRANTS
- WATER LINES
- YARD FOAM HYDRANTS
- ABOVE GROUND FOAM LINES
- BELOW GROUND
- FOAM SYSTEM CONTROL VALVES
- FOAM CHAMBERS & TANKS


NOTE:
FOR DETAILS OF LIQUID FOAM SYSTEM
SEE DWS. 80-24 & 80-25

RECEIVED
JUL 10 8 39 AM '01
INSPECTIONAL
SERVICES


SCALE
0 50 100 150 200

TK202 (2) 10\" vents
203 (2) 10\" vents
204 (2) 10\" vents
TK106 2 (8\" vents)
TK102 1 8\"
103 1 8\"
104 1 8\"

PITTSBON PETROLEUM INC.
CHELSEA MASS.
FIRE PROTECTION
LIQUID FOAM SYSTEM




TERMINAL YARD




SEE FIELD SKETCHES FOR
DETAILS ON DUCT ROUTING

CLIENT:		GLOBAL PETROLEUM		PROJECT:		DDOR ABATEMENT SYSTEM		TITLE:		DUCTING LAYOUT		DVG #		24654 - DUCTING	
PROJECT:		DDOR ABATEMENT SYSTEM		TITLE:		DUCTING LAYOUT		DVG #		24654 - DUCTING		507, 10240 - 124 ST		EDMONTON, ALBERTA	
SCALE:		1" = 10'		DATE:		BY:		REV.		REVISION		507, 10240 - 124 ST		CANADA T5N 3V6	
DATE:		BY:		REV.		REVISION		507, 10240 - 124 ST		CANADA T5N 3V6		7800 413-5334			
REV.		REVISION		507, 10240 - 124 ST		CANADA T5N 3V6		7800 413-5334							



#6 OIL TANK VENT VAPOR CAPTURE



#6 OIL TRUCK FILLING VAPOR CAPTURE

NOTES

DISCLAIMER INFORMATION
 THIS DOCUMENT CONTAINS APPLIED CONTAMINANT CONTROL'S PROPRIETARY AND TRADEDRESS INFORMATION. APPLIED CONTAMINANT CONTROL'S PROPRIETARY AND TRADEDRESS INFORMATION IS NOT TO BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM, WITHOUT THE WRITTEN PERMISSION OF APPLIED CONTAMINANT CONTROL. APPLIED CONTAMINANT CONTROL'S PROPRIETARY AND TRADEDRESS INFORMATION IS NOT TO BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM, WITHOUT THE WRITTEN PERMISSION OF APPLIED CONTAMINANT CONTROL. APPLIED CONTAMINANT CONTROL'S PROPRIETARY AND TRADEDRESS INFORMATION IS NOT TO BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM, WITHOUT THE WRITTEN PERMISSION OF APPLIED CONTAMINANT CONTROL.

CLIENT: CHELSEA-SANDWICH TERMINAL, LLC
 PROJECT: #6 OIL RTO SYSTEM
 TITLE: VAPOR CAPTURE SKETCH
 DATE: MAR, 08

APPLIED CONTAMINANT CONTROL LTD.
 400, 1000 - 101 St
 EDMONTON, ALBERTA
 CANADA T6N 2N5
 (780) 413-8934


DWG # VAPOR CAPTURE

REV. DATE BY

REVISION

RETOX[®] REGENERATIVE THERMAL OXIDIZER SYSTEMS

MAJOR RETOX
RTO OXIDIZER COMPONENTS




- (A) FORCED DRAFT FAN
- (B) POPPET FLOW CONTROL VALVES
- (C) HEAT EXCHANGE BED #1
- (D) BURNER/PIPING TRAIN
- (E) COMBUSTION CHAMBER
- (F) HEAT EXCHANGE BED #2
- (G) EXHAUST STACK
- (H) PLC CONTROLS


ADVEST
TECHNOLOGIES INC.
1175 NORTH VAN HORNE WAY
ANAHEIM, CA 92806-2506
TEL# (714) 632-9801
FAX# (714) 632-9812
www.odwestusa.com

DIMENSIONS				
RTO	A (LENGTH)	B (WIDTH)	C (HEIGHT)	APPROX. WEIGHT LBS.
1,000	8' - 6"	7' - 1"	7' - 1"	9,200
1,500	9' - 8"	7' - 11"	7' - 2"	10,000
2,000	11' - 0"	8' - 5"	7' - 3"	14,400
3,000	12' - 2"	10' - 4"	8' - 1"	18,700
4,000	14' - 0"	10' - 7"	8' - 4"	23,000
5,000	16' - 8"	10' - 10"	8' - 3"	28,800
6,000	19' - 2"	11' - 8"	8' - 11"	33,100
7,500	21' - 0"	12' - 0"	9' - 7"	36,700
9,000	24' - 2"	12' - 8"	10' - 10"	46,300
10,000	26' - 4"	13' - 4"	10' - 10"	49,700
12,000	24' - 0"	15' - 12"	10' - 7"	58,900
13,000	25' - 6"	16' - 2"	10' - 8"	60,400
15,000	25' - 6"	18' - 7"	10' - 11"	68,900
17,500	26' - 10"	21' - 7"	11' - 4"	79,800
20,000	29' - 4"	21' - 11"	11' - 8"	87,300
22,500	32' - 6"	22' - 5"	12' - 0"	94,500
25,000	35' - 8"	22' - 7"	12' - 4"	113,600
27,500	38' - 10"	23' - 0"	12' - 4"	121,400
30,000	42' - 0"	23' - 3"	12' - 4"	129,600
32,500	45' - 2"	23' - 3"	12' - 5"	135,300
35,000	46' - 0"	23' - 3"	12' - 5"	142,800
37,500	42' - 0"	24' - 3"	12' - 4"	148,600
40,000	48' - 0"	24' - 6"	12' - 3"	158,400
42,500	53' - 0"	24' - 6"	12' - 3"	164,400
45,000	48' - 8"	25' - 9"	12' - 3"	169,600
50,000	54' - 6"	26' - 5"	12' - 3"	181,500


zone	description	date	approved



(2) 3" EPA TEST PORTS
90° APART



SIDE ELEVATION VIEW




FRONT ELEVATION VIEW

NOTES:

- 1.- ALL DIMENSIONS ARE W/O FAN AND STACK.
- 2.- PRELIMINARY: NOT TO BE USED FOR CONSTRUCTION.
- 3.- ALL SPECS SUBJECT TO CHANGES W/O NOTICE.
- 4.- WEIGHTS ARE W/O FAN.

ADAMBERT TECHNOLOGIES INC. 13000 S. 10TH AVE. SUITE 100 MESA, AZ 85204 (480) 933-1100 FAX (480) 933-1101 WWW.ADAMBERT.COM		RETORT® RTO OVERALL DIMENSIONS RTO-95 ORIGINAL UNIT	
DATE: 13 JUNE 03 DRAWING NO.: 13000-03 PROJECT NO.: 13000-03 SHEET NO.: 1 OF 1		DESIGNED BY: [blank] CHECKED BY: [blank] APPROVED BY: [blank]	

ADWEST RETOX
REGENERATIVE THERMAL OXIDIZER
MODE OF OPERATION



NOT TO BE REPRODUCED WITHOUT WRITTEN PERMISSION
FROM ADWEST TECHNOLOGIES, INC.

DRAWN BY
R.G.W.

DATE
15 JUN '02

APPROVED BY
RICHARD WHITFORD

TITLE

ADWEST RETOX
REGENERATIVE THERMAL OXIDIZER
MODE OF OPERATION

4 APPLICATION FORMS

This section contains the appropriate Massachusetts DEP “Non-Major Comprehensive Plan Approval” permit application forms (BWP AQ 02) as well as “Comprehensive Plan Approval Application for Non Fuel Utilization Facilities” application forms (BWP AQ CPA-3) and Supplemental Forms for Afterburners (BWP AQ SFP-5) and for Survey of Noise Potential application forms (BWP AQ SFP-3). The corresponding permit fee of \$1,930 has been forwarded to the appropriate post office box in Boston for processing through the proper channels. A list of materials and information required for a complete permit application is contained in Form BWP AQ CPA-3. The location of the required items within this permit application package is as follows:

- | | |
|---|------------|
| • Plot Plan | Section 3 |
| • Topographic Map | Section 3 |
| • Breech/Stack Plan | Section 3 |
| • CPA Forms | Section 4 |
| • Elevation Plan | Section 3 |
| • Emission Calculations | Appendix A |
| • BACT Determination | Section 5 |
| • Standard Maintenance and Operating Procedures | Appendix B |

The remaining information is supplied on the appropriate CPA Forms.



Massachusetts Department of Environmental Protection
Bureau of Waste Prevention – Air Quality
BWP AQ 02 Non-Major Comprehensive Plan Approval
BWP AQ 03 Major Comprehensive Plan Approval
Comprehensive Plan Approval Project Summary Application

W213528

Transmittal Number

1191617

Facility ID (if known)

A. Facility Data

INSTRUCTIONS

This form is to be completed when filing for a comprehensive Plan Approval (CPA). A CPA is required for projects exceeding the thresholds for that of a Limited Plan Approval (LPA) and in other cases as determined by the Department. When filing a CPA, one or more of the following forms is also required according to the type of project.

BWP AQ CPA-1

to

WP AQ CPA-5

or equipment;

BWP AQ SFP-1

to

BWP AQ SFP-5

for VOC

application and

noise;

BWP AQ SFC-1

to

BWP AQ SFC-6

for pollution

control equipment.

1. Chelsea Sandwich LLC

Facility Name

11 Broadway, Chelsea, MA 02150

Location

2. Is the project for a new facility? ☐ Yes ☒ No

3. Previously approved? ☐ Yes ☒ No

If yes, list the previously issued air quality approval(s) for this process and associated emission limits in the table provided.

Application Number

Approval Date

4. Which permit category are you applying for?

☒ BPW AQ 02

☐ BWP AQ 03

B. Applicability

1. **POTENTIAL EMISSIONS** are to be calculated from the maximum capacity of the equipment to emit pollutant under its physical and operational design. Any physical or operational limitation on the capacity of the equipment to emit a pollutant, including air pollution control equipment, restriction on hours of operation, or on the type or amount of material combusted, stored, or processed, shall be treated as part of its design only if the limitation is specifically stated in (a) plan approval(s) or if the facility proposes to incorporate such a restriction into this current plan approval. Fugitive emissions, to the extent quantifiable, are included in determining the potential emissions. Unless otherwise documented, potential emissions shall be based on 8,760 hours per year operation of source.

Current Potential Emissions means the potential emissions for the entire facility as it currently exists. If this is for a new facility, then enter N/A in this column.

Actual Baseline Emissions means the highest actual emissions for the facility in either of the previous two years. If this is for a new facility, then enter N/A in this column.

Proposed Potential Emissions means the potential emissions for this proposed project alone.



Massachusetts Department of Environmental Protection
Bureau of Waste Prevention – Air Quality
BWP AQ 02 Non-Major Comprehensive Plan Approval
BWP AQ 03 Major Comprehensive Plan Approval
Comprehensive Plan Approval Project Summary Application

W213528

Transmittal Number

1191617

Facility ID (if known)

B. Applicability (cont.)

Air Containment*	Current Potential Emissions (TPY)** (after control)	Actual Baseline Emissions (TPY)	Proposed Potential Emissions (TPY) (after control)
Particulate	5.0	1.6	5.0
SO _x	50.1	15.8	50.3
NO _x	35.1	11.0	36.0
VOC	48.3	6.9	37.1
HOC			
Lead			
CO	3.2	1.0	11.8
HAP			5.6
Other			

*Complete only for air quality contaminants that will be affected by this project.

**TPY = tons per year

2. Is this project subject to:

- 310 CMR 7.00 Appendix A- Nonattainment Review? ☐ Yes ☒ No
If yes, also complete section C- Nonattainment Review.
- Was netting used to avoid applicability? ☐ Yes ☒ No
If yes, also complete Section III – Nonattainment Review
- Prevention of Significant Deterioration Permit (PSD)
40 CFR 52.21? ☐ Yes ☒ No
Note: PSD applications are filed with the
U.S. Environmental Protection Agency (EPA).
If yes, also complete section D – PSD.
- Was netting used to prevent PSD? ☐ Yes ☒ No
Note: PSD questions should be directed to EPA.
If yes, also complete section D – PSD.
- New Source Performance Standards (40 CFR 60)? ☐ Yes ☒ No

If yes, which subpart?



Massachusetts Department of Environmental Protection
Bureau of Waste Prevention – Air Quality
BWP AQ 02 Non-Major Comprehensive Plan Approval
BWP AQ 03 Major Comprehensive Plan Approval
Comprehensive Plan Approval Project Summary Application

W213528
Transmittal Number

1191617
Facility ID (if known)

B. Applicability (cont.)

- National Emissions Standards for Hazardous Air Pollutants (NESHAPS) – 40 CFR 61:

☐ Yes

☒ No

If yes, which subpart?

- Maximum Achievable Control Technology (MACT), 40 CFR 63?

☐ Yes

☒ No

If yes, which subpart?

C. Nonattainment Review

This section must be completed only if the construction or modification occurring at the facility is subject to 310 CMR 7.00 Appendix A (Nonattainment Review) **or** would be subject to Nonattainment Review if netting did not occur.

Offsets and Netting

- If the proposed project would be subject to 310 CMR 7.0 Appendix A - Nonattainment Review in the absence of netting, or if emission reduction credits are used as offsets as part of the application, what is being shutdown, curtailed or further controlled to obtain the emission reduction credit (netting is not allowed to avoid review under 310 CMR 7.02):

Emission reduction credits must be part of an enforceable plan approval to be used for either "netting out" or "offsetting emission increases".

Not Applicable

- For the source of emission credits, complete the following table:

Air Containment	Actual Baseline Emissions (TPY)	New Potential Emissions (TPY) (after control)	Emission Reduction Credit (TPY)
<u>Not Applicable</u>	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____

Actual Baseline Emissions means the average actual emissions for the source of emission credits in the previous two years.

New Potential Emissions means the potential emissions for the source of emission credits after project completion.

Emission Reduction Credit means the difference of Actual Baseline and New Potential Emissions.



Massachusetts Department of Environmental Protection
Bureau of Waste Prevention – Air Quality
BWP AQ 02 Non-Major Comprehensive Plan Approval
BWP AQ 03 Major Comprehensive Plan Approval
Comprehensive Plan Approval Project Summary Application

W213528

Transmittal Number

1191617

Facility ID (if known)

C. Nonattainment Review (cont.)

3. If emission reduction credits come from a facility other than where the construction or modification occurs, provide the name and location of the facility:

Not Applicable

D. Affirmative Demonstration of Compliance

The signature below provides the affirmative demonstration pursuant to 310 CMR 7.02 (3) that any facility (ies) in Massachusetts, owned or operated by the proponent for this project (or by an entity controlling, controlled by or under common control with such proponent) that is subject to 310 CMR 7.00, et seq., is in compliance with, or on a Department approved compliance schedule to meet, all provisions of 310 CMR 7.00, et seq., and any plan approval, order, notice of noncompliance or permit issued thereunder. This form must be signed by a responsible official working at the location of the proposed new or modified facility. Even if an agent has been designated to fill out this form, the responsible official must sign it. (Refer to the definition given in 310 CMR 7.00.)

Certification: I certify that I have examined the responses provided herein and that to the best of my knowledge they are true and complete.

Ronald Kenny

Print Name

Ronald W. Kenny

Signature of responsible official

Regional Operations Manager

Position / title

Chelsea Sandwich LLC

Representing

April 11, 2008

Date



Massachusetts Department of Environmental Protection
Bureau of Waste Prevention – Air Quality

BWP AQ CPA-3 (for use with BWP AQ 02, 03)

Comprehensive Plan Approval Application for Non Fuel Emissions

W213528

Transmittal Number

1191617

Facility ID (if known)

A. Applicability

This form is to be used to apply for approval to construct, substantially reconstruct or alter a facility, where the portion of the facility being constructed, substantially reconstructed or altered would result in an increase in potential emissions of equal to or greater than five tons per year of any criteria pollutant, or equal to or greater than five tons per year of any single other air contaminant.

Please note that an emission reduction of the same air contaminant at the facility may not be subtracted from the emissions resulting from the construction, substantial reconstruction or alteration to bring emissions below the five tons per year threshold. Products of combustion from any fuel utilization facility are not included in the sum. Please refer to 310 CMR 7.02(5)

B. Materials that Constitute a Comprehensive Plan Approval Application – Non Fuel Emissions

Proposed projects, which are subject to Comprehensive Plan Approval Application requirements for industrial and commercial facilities, must submit the following items to the appropriate Regional Office for technical review and approval.

- ☒ **Manufacturer's Specifications** and brochures for process equipment, add-on air pollution control equipment, fans/blowers, etc.
- ☒ **Topographic Map** – United States Geodetic Survey (USGS) map, or equivalent, showing the topographic contours for a distance of 1500 feet beyond the boundary lines in every direction. (This may be part of Plot Plan.)
- ☐ **Roof Plan; Building Elevation Plan** – Scaled drawings indicating the locations of all fresh air intakes, windows, and doors.
- ☒ **CPA Forms** should reflect the new or modified process equipment at the facility.
- ☒ **Schematic Process Diagram** – Dimensioned plan showing process equipment, hoods, ductwork, dampers, fans, temperature/pressure sensing devices, other monitors, air pollution control equipment, and all vents, by-passes, or discharges to atmosphere.
- ☒ **Supplemental Forms** for add-on air pollution control equipment fuel equipment, or for volatile organic compounds (VOCs), if applicable.
- ☒ **Calculations** – Detailed calculation sheets showing the manner in which the pertinent quantitative data was determined. This is especially important for calculated emission rates, sizing of air pollution control equipment, and sizing of air moving equipment.
- ☒ **Standard Operating Procedure And Standard Maintenance Procedure** – See section J and section K of this form.
- ☒ **Miscellaneous** – The Department may require other materials if it considers them necessary to the plans review. For example, modeling studies may be required, or monitoring data, or a noise survey. These special items are not usually requested except on the more complex or larger projects.
- ☒ **Plot Plan** – Scaled drawing indicating the outlines of the significant structures within 1500 feet of the building containing this project. Topographic contours may be shown on this plan or on separate plan.
- ☒ **BACT Analysis**
- ☒ **Potential Emissions** – Detailed listing of proposed restrictions limiting potential emissions (see section E).



Massachusetts Department of Environmental Protection
Bureau of Waste Prevention – Air Quality

BWP AQ CPA-3 (for use with BWP AQ 02, 03)

Comprehensive Plan Approval Application for Non Fuel Emissions

W213528

Transmittal Number

1191617

Facility ID (if known)

C. Project Description

1. For the purpose of determining a potential emission rate (or rates), give the maximum operating times proposed for this project.

24

a. hours/day

7

b. days/week

52

c. weeks/year

2. Fully describe the process equipment that will be constructed, substantially reconstructed or altered, identifying:

- a. maximum capacity of process equipment
- b. chemical identity of all raw materials
- c. chemical identity of all finished products
- d. sequence of process events keyed to the Process Diagram required in Section B
- e. process temperatures
- f. process pressures

Use additional sheets of paper if necessary. If volatile organic compounds (VOC) are used in the application of coatings, attach separate formulation sheets and submit a BWP AQ SFP-1 form.

The oil terminal is an existing facility that is installing an emission control device to reduce odors per agreement with the City of Chelsea. The control system will also reduce VOC emissions to assure that the facility remains a minor source.

3. Specify maximum consumption/usage rates of each raw material:

RACK - No. 6 oil - 500 million gal/yr, No. 2 oil - 438 million gal/yr, Kerosene - 15 million gal/yr

BARGE - No. 6 oil - 60 million gal/yr, No. 2 oil - 60 million gal/yr, Kerosene - 10 million gal/yr

4. Describe storage/handling procedures for raw materials:

No. 6 oil is stored in heated fixed roof tanks. No.2 oil/kerosene is stored in non-heated fixed roof tanks.



Massachusetts Department of Environmental Protection
Bureau of Waste Prevention – Air Quality

BWP AQ CPA-3 (for use with BWP AQ 02, 03)

Comprehensive Plan Approval Application for Non Fuel Emissions

W213528

Transmittal Number

1191617

Facility ID (if known)

C. Project Description (cont.)

5. Specify maximum production rate(s) of finished products:

Same as raw materials.

6. Describe storage/handling procedures for finished products:

Same as raw materials.

7. Describe features of equipment layout designed to allow for future growth, emission control device add-on, or stack testing ports:

The maximum flow capacity of the emission control device is approximately twice the capacity
currently required.

8. Describe how fugitive emissions will be minimized especially during process upsets, or disruptions:

The capture system is designed for an exhaust rate capable of handling the most emissive tanks
events, i.e., filling at a maximum pump rate. (See Process Description – Section 2)

9. Explain those aspects of the design that have been required because of other environmental concerns, or safety concerns, or other regulations, such as; construction materials handling practices system interlocks, waste disposal procedures, etc.:

The initial purpose of the control system was to reduce odors through the collection and control of
total reduced sulfur (TRS) compounds from the heated residual oil tanks and rack loading lanes.

The proposed control system will additionally control VOC emissions



Massachusetts Department of Environmental Protection
Bureau of Waste Prevention – Air Quality

BWP AQ CPA-3 (for use with BWP AQ 02, 03)

Comprehensive Plan Approval Application for Non Fuel Emissions

W213528

Transmittal Number

1191617

Facility ID (if known)

D. Emissions Data

1. Maximum Gaseous Emissions Rates:

Chemical Name	Before Control (pounds/hour)	After Control (pounds/hour)	After Control (ppm of volume)
VOC Control Exhaust	66	0.63	20
a.			
VOC fugitive		3.7	
b.			
TRS Control Exhaust	.24	0.002	0.1
c.			
TRS fugitive		0.013	
d.			

2. Maximum Particulate Emissions Rates:

Chemical Name	Before Control (pounds/hour)	After Control (pounds/hour)	After Control (grains/DSCF)*
Not Applicable			
a.			
b.			
c.			

* grains per dry standard cubic foot

3. Indicate how the above emission rates were obtained, and attach appropriate calculations and documentation:

Testing using Methods 25, 25A and TO-3 for VOC

Testing using Method ASTM D 5504-1 for TRS

4. a. Describe the potential for visible emissions (opacity) from this project:

None

b. Describe the potential for odor impacts from this project:

The purpose of the control system being proposed is to reduce odors.



Massachusetts Department of Environmental Protection
Bureau of Waste Prevention – Air Quality

BWP AQ CPA-3 (for use with BWP AQ 02, 03)

Comprehensive Plan Approval Application for Non Fuel Emissions

W213528

Transmittal Number

1191617

Facility ID (if known)

E. Potential Emissions

POTENTIAL EMISSIONS are used to determine applicability to air pollution control regulations and compliance fees. Unless otherwise restricted, potential emissions are calculated from the maximum operational capacity of the equipment as described in section C operated 8,760 hours per year. If you wish to limit potential emissions you must complete this section; this will be treated as part of the facility design and the limitation will be specifically stated in this Plan Approval.

1. In order to issue a permit limiting the facility's potential emissions, the Department must have a method to monitor compliance with the restriction. In other words, an enforceable permit condition must be available to the Department. The following questions require the facility to set a limit on the maximum amount of raw materials used (per month and per year) and therefore, the maximum amount of emissions possible. This will become the means to monitor and enforce the restriction. Alternative methods of restricting potential emissions will be evaluated on a case-by-case basis and the applicant should contact the Department before proposing such alternatives. Any such alternative method must be consistent with the U.S. EPA's June 13, 1989 guidance entitled, "Guidance on Limiting Potential to Emit in New Source Permitting". (Copies of this guidance are available from DEP offices).

Note:
This raw material restriction will become the facility's allowable usage. This amount can never be exceeded without prior Department approval.

	Raw Material	Amount Used in Equipment 1		Amount Used in Equipment 2		Amount Used in Equipment 3		Total Used	
		per month	per year	per month	per year	per month	per year	per month	per year
R	Kerosene	25 m	50 m					25 m	50 m
	No. 2 oil	219 m	438 m					219 m	438 m
	No. 6 oil	250 m	500 m					250 m	500 m
B	Kerosene	5 m	10 m					5 m	10 m
	No. 2 oil	30 m	60 m					30 m	60 m
	No. 6 oil	30 m	60 m					30 m	30 m

m = million gallons

R = Rack

B = Barge

2. Describe any other physical or operational limitation on the capacity of the equipment to emit a pollutant, including air pollution control equipment, restriction on hours of operation, or on the type or amount of material combusted, stored or processed that will be used to restrict emissions:

Byproducts of combustion emissions from the RTO reflect the maximum natural gas use based on

the burner size and 8,760 hours per year.



Massachusetts Department of Environmental Protection
Bureau of Waste Prevention – Air Quality
BWP AQ CPA-3 (for use with BWP AQ 02, 03)
Comprehensive Plan Approval Application for Non Fuel Emissions

W213528
Transmittal Number
1191617
Facility ID (if known)

F. Air Pollution Control Equipment

If new air pollution control equipment is proposed or if existing control equipment will be modified or affected by this project, then an equipment specific Supplemental Form must be submitted.

1. Is Emission Control System:

☒ Proposed?

☐ None?

Existing? (if existing, supply previous Approval number)

Regenerative Thermal Oxidizer (RTO) being proposed.

a. If proposed or existing, describe:

A carbon system initially designed to remove Total Reduced Sulfurs (TRS) is being replaced.

b. If existing, described purpose changed:

2. Control Efficiency:

Capture Efficiency (CE)

90 for Residual Oil Truck Loading, 95 for Residual Oil Tanks

Percent by weight pollutants captured by the ventilation system

Destruction Efficiency (DE)

99

Percentage by weight pollutants destroyed or captured in control device

Overall Control Efficiency:

89 for Residual Oil Truck Loading, 94 for Residual Oil Tanks

Percentage by weight of overall efficiency of the control system (CE X DE)/100

Describe how capture efficiency was derived:

Estimate provided by design engineer based on configurator and design capture velocity.

3. Does this application represent Best Available Control Technology (BACT) as stated in Regulation 310 CMR 7.02 (3)(j)6?

☒ Yes

☐ No

a. If yes, is required supplementary documentation attached?

☒ Yes

☐ No

b. If no, explain why this project is exempt:



Massachusetts Department of Environmental Protection
Bureau of Waste Prevention – Air Quality

BWP AQ CPA-3 (for use with BWP AQ 02, 03)

Comprehensive Plan Approval Application for Non Fuel Emissions

W213528

Transmittal Number

1191617

Facility ID (if known)

G. Air Handling System

This section is for the description of fans and those flow parameters associated with the processes and/or the air pollution control equipment.

	Fan A	Fan B	Fan C
1. Identify fan (from process schematic)	RTO Fan		
2. Fan Manufacturer	Air Pro Fan		
3. Fan Model Number	IEAH 447		
4. Fan Type (axial, centrifugal etc.)	Centrifugal		
5. Capacity (in SCFM)	9,000		

Manufacturer's fan performance curve or rating curve, with operating point indicated, must be submitted with this application if the fans are an integral part of the installed or modified equipment.

6. Fan Operating Point in this System	Fan A	Fan B	Fan C
a. Actual RPM	1,750		
b. Temperature at the fan (°F)	Ambient		
c. Fan pressure (static pressure, in H ₂ O)	30		
d. Actual flow rate of fan (ACFM)	12,400		
e. Actual horsepower requirements	69 bhp		

H. Miscellaneous Data

- Number of employees at this facility
11
- Standard Industrial Classification (SIC) Code for this facility
5171
- Does municipal water supply to your process operations have the required back-flow preventer?

☒ Yes ☐ No

If Yes, is it registered with the DEP Division of Water Supply?

— —




Massachusetts Department of Environmental Protection
Bureau of Waste Prevention – Air Quality
BWP AQ CPA-3 (for use with BWP AQ 02, 03)
Comprehensive Plan Approval Application for Non Fuel Emissions

W213528
Transmittal Number

1191617
Facility ID (if known)

I. Exhaust Stack Description



Questions for the above diagram

10ft.

1. Height of Ground Above Sea Level (arrow 1)

5ft.

3. Height of Stack Top above Roof (arrow 3)

10ft.

5. Height of Stack Top above Control Equip. (arrow 5)

RTO Stack

7. Identify Stack Nos. as they appear on Process Schematic

Carbon Steel

9. Outside Shell Material

Ambient to 160

11. Range of stack gas exit temp. (°F)

None

13. Type of Rain Protection

20ft.

2. Height of Stack Top above Ground (arrow 2)

20in.

4. Stack Exit Size (inside) (arrow 4)

Vertical

6. Discharge direction (horizontal or vertical)

Carbon Steel

8. Inside shell material

0 to 81.6

10. Range of gas exit velocity (ft/sec)

0 to 10,678

12. Range of stack gas volume (acfm)


The stack parameters will be evaluated to assure they provide sufficient protection from building, terrain, and stack tip downwash effects. Also, the "dew point" of the exhaust gases will be considered in the evaluation.

Note: The rain protection device should be of such a design as to allow the unimpeded escape of the stack gases. "Rain Hats" are prohibited.

J. Standard Operating Procedure

Describe the start-up, operational, shutdown, and emergency procedures for the equipment that is integral to this project. The inscription must present, in sequence, the major steps that must be taken by the operator(s) to correctly and safely run the system. For each step, specify the duration and purpose, especially as it relates to maintaining safe operation and minimizing the emission of air contaminants. This inscription must detail the inter-relationship of the timing devices, the temperature indicators, the pressure indicators, the flow rate indicators, etc. **Specify which steps are under manual control and which are under automatic control.** Discuss the types, amounts, and duration of the release(s) of air contaminants during system fluctuations. Specify what measurements are observed and recorded to monitor performance. Use additional paper if necessary.

See Appendix B



1191617
Facility ID (if known)

Describe preventive maintenance procedures for this **entire system**. Include such items as cleaning, part replacement, scrubbing solution renewal/replacement schedules, method of leak testing, frequency of leak testing and/or effluent sampling to establish adequacy of control systems. Include Manufacturer's maintenance requirements. Each air pollution control device requires a separate and detailed maintenance procedure. You are required to keep organized records at the facility that will document the monitored operating parameters, and the history of maintenance activities for the most recent two-year period. Describe your proposed record keeping system. Use additional paper if necessary.

See Appendix B



Massachusetts Department of Environmental Protection
Bureau of Waste Prevention – Air Quality
BWP AQ CPA-3 (for use with BWP AQ 02, 03)
Comprehensive Plan Approval Application for Non Fuel Emissions

W213528
Transmittal Number

1191617
Facility ID (if known)

L. Plans Application Preparer

1. Stephen Piper, P.E.
Person who compiled the plans application materials
2. M.J. Bradley & Associates, Inc.
Representing
3. 1000 Elm Street, Second Floor, Manchester, NH 03101
Address
4. 603-647-5746 ext 102
Telephone number
5. April 7, 2008
Date completed

M. Certification

The seal and signature of a Massachusetts registered professional engineer must be entered below. This certifies that the information contained in this form has been checked for accuracy, and that the design represents good air pollution control engineering practice. (These must be originals. No photocopies, etc., of the seal and signature will be accepted.)


Stephen Piper
Print name

[Signature]
Authorized signature

M.J. Bradley & Associates, Inc.
Representing

4/11/08
Date

Senior Project Manager
Position/title




36039
PE number



Massachusetts Department of Environmental Protection
Bureau of Waste Prevention – Air Quality Control
BWP AQ SFC-5 (for use with BWP AQ 02, 03)
Supplemental Forms for Afterburners

W213528
Transmittal Number
1191617
Facility

Important: When filling out forms on the computer, use only the tab key to move your cursor - do not use the return key.



A. Plans Applications Requirements

This form is to be submitted together with Form BWP AQ CPA-3, prior to the modification or the installation of an **Afterburner**.

B. Project Location

Chelsea Sandwich LLC

Name of facility

11 Broadway

Street/PO Box

Chelsea

City/town

MA

State

02150

Zip code

C. Equipment Specifications

Adwest Technologies

1. Manufacturer

RETOX 9.0 RT095

2. Model number

3. Is the unit, ☒ Thermal? ☐ Catalytic?

4. What is the capacity (SCFM) of the unit?

9,000

5. Give the combustion chamber dimensions:

Square

23.6

a. What is the cross-sectional shape (round, square, etc)?

b. What is the cross-sectional area (sq. ft.)?

22.7

535

c. What is the chamber length (ft.)?

d. What is the effective chamber volume (ft.)?

6. Is there a pre-mixing chamber? ☒ Yes ☐ No

The ceramic beds that provide heat recovery as the air is reversed.

If yes, describe

7. Mixing occurs in the fume fan initially as well as the ceramic beds.

How is the combustion chamber designed to maximize mixing?

8. Give the following information for the catalytic unit:

Not Applicable

a. Give a brief description of the catalyst:

b. What are the dimensions of the bed?

height (in.)

width (in.)

depth (in.)

weight (lbs.)

9. Describe the afterburner's materials of construction:

Silica / Alumina Media

6 - Insulation

a. What is the type of refractory?

b. What is the thickness of the materials (in.)?

Plate

10

c. What is the shell material?

d. What is the expected life of the unit (yrs.)?



Massachusetts Department of Environmental Protection
Bureau of Waste Prevention – Air Quality Control
BWP AQ SFC-5 (for use with BWP AQ 02, 03)
Supplemental Forms for Afterburners

W213528
Transmittal Number
1191617
Facility

D. Fuel and Burner Data

1. List the burner manufacturer(s) and model numbers:

Adwest Technologies
Manufacturer

RETOX 9.0 RTO095
Model number

2. What type of fuel is used?

Natural Gas
natural gas, oil, other

Note: fuel oil will be permitted only where natural gas is unavailable, only distillate fuel oil may be used if it is necessary to burn oil.

3. If gas is used, is it: ☒ Natural gas?

☐ Propane?

a. What is the firing rate of the gas (cu. ft./hr.)?

2,584 cu ft/hr
Max

0

Min

b. What is the maximum heat input rate (Btu/hr)?

720,000

4. If fuel oil is used, indicate:

Not Applicable

a. What is the type of oil?

b. What is the % sulfur by weight?

c. What is the maximum fuel firing rate (gal/hr)?

d. What is the minimum fuel firing rate (gal/hr)?

e. What is the maximum heat input rate (Btu/hour)?

5. What is the % excess combustion air?

Combustion air in fume stream

6. Describe burner design and explain how proper mixing of fuel and combustion air is achieved:

The RTO has natural gas injection at the collection fan inlet. Supplemental fuel is added to the fume stream, passes through the fan and is introduced to pre-heat the ceramic bed.

7. Describe burner modulation system (full modulating, high/low, on/off, etc.):

NGI system is fully modulating to maintain the minimum destruction temperature.

8. If on/off modulation is used, explain how minimum operating temperature will be maintained at all times:

Not Applicable

9. What portion of the contaminant stream will by-pass the burner to be mixed with the flame downstream?

None. 100% of the stream passes through the heat exchangers and through the reaction chamber.



Massachusetts Department of Environmental Protection
Bureau of Waste Prevention – Air Quality Control

BWP AQ SFC-5 (for use with BWP AQ 02, 03)

Supplemental Forms for Afterburners

W213528

Transmittal Number

1191617

Facility

E. Operating Parameters

- | | |
|--|--|
| 1. Contaminant stream inlet flow rate: | <u>9,300</u>
ACFM, wet |
| 2. Inlet moisture: | <u>Assume at 50% RH typical</u>
lbs./min. |
| 3. Temperature at the afterburner inlet and outlet: | <u>80</u>
Inlet (°F)
<u>280</u>
Outlet (°F) |
| 4. Static pressure at the inlet and outlet: | <u>Approx +14</u>
Inlet - inches of water
<u>Approx +0.5</u>
Outlet - inches of water |
| 5. If catalytic, pressure drop across the bed: | <u>Not Applicable</u>
inches of water |
| 6. Outlet exhaust gas flow rate: | <u>12,400</u>
ACFM, wet |
| 7. Minimum combustion temperature, as measured at the downstream end of the combustion | <u>1,500</u>
°F |
| Note: The burner must be able to maintain this minimum operating temperature without benefit of the heating value of contaminants in the waste stream. | |
| 8. Combustion chamber temperature control mechanism: | <u>Multiple thermocouples monitored by PLC</u> |
| 9. Minimum residence time of gases in the combustion chamber at the minimum | <u>1.0</u>
Seconds
<u>1,500</u>
(°F) |

Note: Design calculations must be submitted which incorporate fuel, air, and waste stream supply rates as well as heat transfer phenomenon (including heat recovery systems) in the determination of the minimum gas temperature and residence time in the combustion chamber.

10. Explain the design and operation of any heat recovery system associated with this afterburner system:

There are ceramic beds at either end of the combustion chamber. Air flow is reversed every 3-5 min for heat recovery.

11. Attach a dimensioned plan(s) of the process and afterburner system. Indicate the location(s) of the burner(s), catalyst bed(s), bypass damper(s), bypass stack, and the normal stack. Clearly indicate the gas circulation pattern through preheat and burner chambers, and through heat recovery unit(s) prior to ambient discharge. Sampling ports for emission testing must also be indicated.

12. How many plans are attached?

4 (See Section 3)

13. Describe features of the system design and operation which will allow for emission testing using Department-sanctioned test methods:

C/W 2, 4 inch FPT ports at 90 degrees located minimum 8 diameters from the stack inlet.



Massachusetts Department of Environmental Protection
Bureau of Waste Prevention – Air Quality Control

BWP AQ SFC-5 (for use with BWP AQ 02, 03)

Supplemental Forms for Afterburners

W213528

Transmittal Number

1191617

Facility

F. Afterburner Operating Controls

1. List and explain all of the operating and safety controls associated with this system (include thermocouples and associated indicators/controlling pyrometers, interlock systems which prevent introduction of the waste stream until the afterburner achieves the minimum operating temperature, pilot flame detection devices, timing devices controlling purge of afterburner prior to burner ignition, high temperature limit controls, pressure switches to detect low fuel pressure or low air pressures, LEL monitors, bypass activation mechanisms, alarms, etc.). (Use a separate sheet of paper if necessary.)

See Appendix B

2. Explain the typical process fluctuations such as changes in process rate, effluent temperatures, flow rates, fume concentrations, etc., which may affect operation of the unit. Also explain the means by which control efficiency will be maintained throughout these fluctuations:

See Appendix B

3. What are the emergency procedures during system upsets?

See Appendix B

G. Emissions Data

The Applicant Must Provide Detailed Information on the Presence of the Following Substances in the Contaminated Gas Stream: chlorines, other halogens, sulfur, heavymetals, asbestos.

1. Indicate the maximum gaseous emission rate:

Chemical Name	Before Control (lbs./hr)	After Control (lbs./hr)	After Control (ppm by volume)
VOC	66	0.63	20
a.			
TRS	0.24	0.002	0.1
b.			
c.			



Massachusetts Department of Environmental Protection
Bureau of Waste Prevention – Air Quality Control
BWP AQ SFC-5 (for use with BWP AQ 02, 03)
Supplemental Forms for Afterburners

W213528
Transmittal Number
1191617
Facility

G. Emissions Data (cont.)

2. Indicate the maximum particulate emissions rate:

Chemical Name	Before Control (lbs./hr)	After Control (lbs./hr)	After Control (ug/DSCM)
Not Applicable			
a.			
b.			
c.			
d.			

3. Indicate how the above emission rates were obtained, and attach appropriate calculations and documentation:

VOC and TRS based on test data.

4. What is the capture efficiency of the ventilation systems serving the afterburner?

90 for truck loading, 95 for tank vents Estimated based on design
% And how was this calculated or determined?

5. What is the destruction efficiency of organic compounds (as carbon) in the afterburner?

99.0 Vendor guarantee
% And how was this calculated or determined?

H. Catalytic Units Only

1. Estimated useful life of the catalyst: Not Applicable
2. How will catalyst performance be monitored? _____
3. Will the used catalyst be treated for re-use? ☐ Yes ☐ No
4. If not, how will it be disposed of? _____
5. Is the used catalyst subject to 310 CMR 30.000 pertaining to Hazardous Waste? ☐ Yes ☐ No
6. If yes, identify the disposal agency: _____

License number



Massachusetts Department of Environmental Protection
Bureau of Waste Prevention – Air Quality Control
BWP AQ SFC-5 (for use with BWP AQ 02, 03)
Supplemental Forms for Afterburners

W213528
Transmittal Number
1191617
Facility

I. Failure Notification

1. How is the failure of the collection device made known to the operator (e.g. audible alarm, lights, etc.)?

Audible alarm representing fan failure

Local inlet gauges confirm capture system airflow

See Appendix B

2. Describe the record keeping procedures to be used in identifying the cause, duration, and resolution of each failure (use a separate page if necessary):

Operator Log Book

J. Certification

The seal and signature of a Massachusetts Registered Professional Engineer must be entered below. This certifies that the information contained in this form has been checked for accuracy, and that the design represents good air pollution control engineering practice. (These must be originals; no photocopies, etc. of the seal and signature will be accepted.)

Stephen Piper

Print name

Authorized signature

Senior Project Manager

Position/title


M.J. Bradley & Associates, Inc.

Representing

Date

36039

PE number





Massachusetts Department of Environmental Protection
Bureau of Waste Prevention – Air Quality Control

BWP AQ SFC-7 (for use with BWP AQ CPA-1
through BWP AQ CPA-5)

W213528

Transmittal Number

1191617

Facility

Important:
When filling out
forms on the
computer, use
only the tab key
to move your
cursor - do not
use the return
key.



Determination of Best Available Control Technology

A. Applicability

Complete this form only if specifically requested to do so by the Department. Do not complete this without first consulting with the regional office. This form is not a requirement of all applicants. This form is intended as a supplement to forms BWP AQ CPA-1 through BWP AQ CPA-5 where the applicant is required to demonstrate that the source will utilize Best Available Control Technology (BACT) for the emission of a pollutant. This analysis utilizes the "top-down" approach to determination of BACT.

For additional guidance on the determination of BACT, refer to the June 1991 NESCAUM BACT GUIDELINE, attached to this form.

B. General

Chelsea Sandwich LLC

Facility name

11 Broadway Chelsea, MA 02150

Location

C. Pollutants

For the process under review, list each pollutant or class of pollutant that will be emitted and the **baseline (uncontrolled)** emission rate. These values should agree with values provided on CPA or other forms filed with this application.

Pollutant

Uncontrolled Emission Rate

Pounds per Hour*

Tons per Year**

Sulfur Dioxide (SO₂):

See Section 5

Nitrogen Oxides (NO_x):

Carbon Monoxide (CO):

Lead (Pb):

Particulates (PM):

Volatile Organic Compounds (VOC):

Other Pollutants (list):

1.

2.

3.

*Pounds per hour
is the maximum
emission rate
possible for the
process.

**Tons per year is
calculated from
pounds per hour
operating 8760
hours per year
unless otherwise
restricted (i.e. by
a federally
enforceable limit
or permit on
operation or
production).



Massachusetts Department of Environmental Protection
Bureau of Waste Prevention – Air Quality Control
BWP AQ SFC-7 (for use with BWP AQ CPA-1
through BWP AQ CPA-5)

W213528
Transmittal Number
1191617
Facility

Determination of Best Available Control Technology

D. Control Options

List, in order of resulting emission rates (1 = lowest, 6 = highest), all air pollution control measures and/or devices which would result in a lower emission rate than that of the project, as proposed. Do not, at this time, eliminate from consideration any options because of economics, technical or other considerations. See the last page of this form (section J) for some examples of control options; it is not, however, a comprehensive list.

You must include:

- technology required by any regulations;
- technology that is in use on similar types of sources (existing control technology);
- technology that is in use on other types of sources but not yet demonstrated specifically on your source (technology transfer);
- theoretically applicable technology but as yet unproven on full scale installations;
- add-on control equipment;
- process modifications that will reduce emissions;
- alternative raw materials; and
- alternative fuels.

Control Description	Emission Rate After Controls (pounds per hour)		
	Pollutant 1*	Pollutant 2*	Pollutant 3*
1. _____	_____	_____	_____
2. _____	_____	_____	_____
3. _____	_____	_____	_____
4. _____	_____	_____	_____
5. _____	_____	_____	_____
6. _____	_____	_____	_____

*Indicate pollutant



Massachusetts Department of Environmental Protection
Bureau of Waste Prevention – Air Quality Control

BWP AQ SFC-7 (for use with BWP AQ CPA-1
through BWP AQ CPA-5)

W213528
Transmittal Number

1191617
Facility

Determination of Best Available Control Technology

E. Option Feasibility

For each control option listed above, indicate the reason for not utilizing the option in this project and whether or not the technology has been demonstrated in use by a similar source.

Control Option	Basis of Elimination			Demonstrated in Use	
	Economic	Technical	Other	Yes	No
1.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
3.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
4.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
5.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

* Indicate Pollutant

F. Documentation

For each basis of elimination checked in section E on the previous page, provide a detailed explanation or calculation to substantiate the elimination of the control option. The substantiation shall include those items as delineated below:

Technical: Elimination based on technical grounds must specifically state the reason the technology is not feasible and why the system cannot be modified to accommodate the source. If the technology is in use on other sources, the difference prohibiting its use on this source must be stated in detail. Do not use cost or other qualifications in the technical documentation. **Be as specific and technical as possible.**

Economic: Elimination based on economic (cost of the control) must complete the Cost Analysis work sheet, section I. Approximations/estimates may be used as necessary. However, in the event that the Department does not concur with provided estimates, final determination of cost will be based on procedures outlined in the OAQPS Control Cost Manual (EPA Document 450/3-90-006) or other methods approved by the Department.

Other: Elimination based on other considerations must specifically state the reason the option is not feasible and why the system cannot be modified to accommodate this option. **Be as specific and detailed as possible.**



Massachusetts Department of Environmental Protection
Bureau of Waste Prevention – Air Quality Control
BWP AQ SFC-7 (for use with BWP AQ CPA-1
through BWP AQ CPA-5)

W213528
Transmittal Number
1191617
Facility

Determination of Best Available Control Technology

G. Additional Impacts

Describe other factors, beneficial and adverse, associated with the project and/or control option as appropriate. Include items such as:

Environmental Impacts – Describe environmental factors other than mass emissions to the air that are relevant, such as:

- visible emissions
- odor
- toxicity of emissions
- noise
- safety

Energy Impacts – Describe factors such as:

- energy consumption of different options
- impact of alternative fuel use

Impact on other media - Describe cross media impacts, such as:

- water pollution
- water supply
- solid waste
- hazardous waste, etc.

H. BWP SFC – 7 Preparer

Stephen Piper, PE

Name

M.J. Bradley & Associates

Company

1000 Elm St. Second Floor

Address

Manchester

City/town

603-647-5746 ext. 102

Telephone number

NH

State

April 11, 2008

Date

03101

Zip code

I. Cost Analysis Work Sheet

Total Capital Investment (TCI)

Direct Purchase Cost

1. Primary control device auxiliary equipment

2. Fans

3. Ducts

4. Other

5. Instrumentation/controls

Indirect Capital Cost

6. Construction

7. Labor

8. Sales taxes*

9. Freight charges



Massachusetts Department of Environmental Protection
Bureau of Waste Prevention – Air Quality Control

BWP AQ SFC-7 (for use with BWP AQ CPA-1
through BWP AQ CPA-5)

W213528
Transmittal Number

1191617
Facility

Determination of Best Available Control Technology

I. Cost Analysis Work Sheet (cont.)

Engineering/Planning

10. Contracting fees

11. Testing

12. Supervision

13. Total capital investment (add items 1 – 12)

14. Annualized capital cost

$$C[i(1+i)^n]/[(1+i)^n - 1]$$

i = interest rate (assume 10%)

n = life of equipment (assume 10 years or less)*

C = Total Capital Investment (line 13)

Annual Operating and Maintenance Cost

Direct Operating Cost

15. Labor

16. Maintenance

17. Replacement parts

Indirect Cost

18. Property taxes*

19. Insurance

20. Fees

21. Total annual operating costs (add items 15 – 20)

Energy Cost

22. Annual electrical energy expense

23. Annual auxiliary fuel

24. Total annual energy cost (item 22 + 23)

25. Annual waste treatment and disposal costs

26. Miscellaneous annual expenses

27. Annual recourse recovery & resale

28. Total annualized control costs
(items 14+21+25+26)-27

29. Amount of pollutant controlled over Baseline Emissions
(Tons per year)

30. Cost of control (\$/ton) (divide 28 by 29)

*State and federal law may provide for certain tax exemptions and special loans for the purchase of control equipment. Contact the Massachusetts Industrial Finance Agency (MIFA) or Federal Small Business Association (SBA).



Massachusetts Department of Environmental Protection
Bureau of Waste Prevention – Air Quality Control
BWP AQ SFC-7 (for use with BWP AQ CPA-1
through BWP AQ CPA-5)

W213528
Transmittal Number
1191617
Facility

Determination of Best Available Control Technology

J. Control Options (Partial list)

ADD-ON CONTROLS

- Thermal Incinerators
- Catalytic Incinerators
- Fabric Filters/Baghouses
- Cyclones
- Electrostatic Precipitators
- Condenser/Refrigeration Systems
- Wet Scrubbers:
 - Packed Bed
 - Spray Chamber
 - Other
- Carbon Adsorbers
- Other Media Adsorbers
- Dry Scrubbers
- Flares
- Non-Regenerative Carbon
- Biofilters/Soil Filters
- Non-Selective Catalytic Reduction
- Selective Catalytic Reduction
- Afterburners
- Other Add-on Control Devices

PROCESS MODIFICATION

- Reformulation of Raw Materials
- Use of Non-Hazardous/Non-Toxic Alternatives
- Combustion Controls
- Alternate Processing Techniques
- Electrostatic Spray Application
- High Volume Low Pressure (HVLP) Spray Application
- Recycling/Waste Minimization
- Alternative Fuels
- Powder Coating
- Aqueous Cleaning Compounds
- Other Process Changes



Massachusetts Department of Environmental Protection
Bureau of Waste Prevention – Air Quality

BWP AQ SFP-3 (for use with BWP AQ 02, 03)

Supplemental Form for Survey of Noise Potential

W213528

Transmittal Number

1191617

Facility

Important:

When filling out forms on the computer, use only the tab key to move your cursor - do not use the return key.



A. Plans Application Requirements

This form is to be submitted together with BWP AQ CPA 03 and BWP AQ CPA 01, *prior* to the modification or the installation of equipment (such as diesel engines, electric generators, or turbines) which has the potential to cause a noise nuisance condition, or a submittal in response to a Department **Notice of Noncompliance** citing a noise nuisance condition.

B. Noise Source

1. Description:

RTO – See Section 2 and Appendix D

2. Indicate operating schedule:

a. hours/day

b. days/week

c. weeks/year

3. Comments:

C. Noise Abatement Equipment

1.

Manufacturer

Model number

2. Describe type, location, performance characteristics:



Massachusetts Department of Environmental Protection
Bureau of Waste Prevention – Air Quality

BWP AQ SFP-3 (for use with BWP AQ 02, 03)

Supplemental Form for Survey of Noise Potential

W213528

Transmittal Number

1191617

Facility

D. Full Octave Band Analysis

The following community noise profiles will require the use of sound pressure level measuring equipment in the neighborhood of the installation.

1. Lowest **Ambient** Sound Pressure Levels During Operating Hours of Noise Source.

a. At property line:

<u>"A" Weighted</u>	<u>31.5</u>	<u>63.0</u>	<u>125</u>	<u>250</u>	<u>500</u>	<u>1K</u>	<u>2K</u>	<u>4K</u>	<u>8K</u>	<u>16K</u>
_____	_____	_____	_____	_____	_____	_____	_____	_____	_____	_____
_____	_____	_____	_____	_____	_____	_____	_____	_____	_____	_____
_____	_____	_____	_____	_____	_____	_____	_____	_____	_____	_____
_____	_____	_____	_____	_____	_____	_____	_____	_____	_____	_____

b. At the nearest inhabited building:

<u>"A" Weighted</u>	<u>31.5</u>	<u>63.0</u>	<u>125</u>	<u>250</u>	<u>500</u>	<u>1K</u>	<u>2K</u>	<u>4K</u>	<u>8K</u>	<u>16K</u>
_____	_____	_____	_____	_____	_____	_____	_____	_____	_____	_____
_____	_____	_____	_____	_____	_____	_____	_____	_____	_____	_____
_____	_____	_____	_____	_____	_____	_____	_____	_____	_____	_____
_____	_____	_____	_____	_____	_____	_____	_____	_____	_____	_____

The following noise profiles are required only for a submittal in response to a department **Notice of Noncompliance** citing a noise nuisance condition. Applications for new equipment can skip this section and go ahead to section D3.

2. Neighborhood Sound Pressure Levels with Source Operating without Abatement Equipment.

a. At property line:

<u>"A" Weighted</u>	<u>31.5</u>	<u>63.0</u>	<u>125</u>	<u>250</u>	<u>500</u>	<u>1K</u>	<u>2K</u>	<u>4K</u>	<u>8K</u>	<u>16K</u>
_____	_____	_____	_____	_____	_____	_____	_____	_____	_____	_____
_____	_____	_____	_____	_____	_____	_____	_____	_____	_____	_____
_____	_____	_____	_____	_____	_____	_____	_____	_____	_____	_____
_____	_____	_____	_____	_____	_____	_____	_____	_____	_____	_____



Massachusetts Department of Environmental Protection
Bureau of Waste Prevention – Air Quality

BWP AQ SFP-3 (for use with BWP AQ 02, 03)

Supplemental Form for Survey of Noise Potential

W213528

Transmittal Number

1191617

Facility

D. Full Octane Band Analysis (cont.)

b. At the nearest inhabited building:

<u>"A" Weighted</u>	<u>31.5</u>	<u>63.0</u>	<u>125</u>	<u>250</u>	<u>500</u>	<u>1K</u>	<u>2K</u>	<u>4K</u>	<u>8K</u>	<u>16K</u>
_____	_____	_____	_____	_____	_____	_____	_____	_____	_____	_____
_____	_____	_____	_____	_____	_____	_____	_____	_____	_____	_____
_____	_____	_____	_____	_____	_____	_____	_____	_____	_____	_____
_____	_____	_____	_____	_____	_____	_____	_____	_____	_____	_____

3. **Expected** Neighborhood Sound Pressure Levels after Installation of Noise Abatement Equipment.

a. At property line:

<u>"A" Weighted</u>	<u>31.5</u>	<u>63.0</u>	<u>125</u>	<u>250</u>	<u>500</u>	<u>1K</u>	<u>2K</u>	<u>4K</u>	<u>8K</u>	<u>16K</u>
_____	_____	_____	_____	_____	_____	_____	_____	_____	_____	_____
_____	_____	_____	_____	_____	_____	_____	_____	_____	_____	_____
_____	_____	_____	_____	_____	_____	_____	_____	_____	_____	_____
_____	_____	_____	_____	_____	_____	_____	_____	_____	_____	_____

b. At nearest inhabited building:

<u>"A" Weighted</u>	<u>31.5</u>	<u>63.0</u>	<u>125</u>	<u>250</u>	<u>500</u>	<u>1K</u>	<u>2K</u>	<u>4K</u>	<u>8K</u>	<u>16K</u>
_____	_____	_____	_____	_____	_____	_____	_____	_____	_____	_____
_____	_____	_____	_____	_____	_____	_____	_____	_____	_____	_____
_____	_____	_____	_____	_____	_____	_____	_____	_____	_____	_____
_____	_____	_____	_____	_____	_____	_____	_____	_____	_____	_____

Note: The Department may request that actual measurements be taken after the installation of the noise abatement equipment to verify compliance.



Massachusetts Department of Environmental Protection
Bureau of Waste Prevention – Air Quality

BWP AQ SFP-3 (for use with BWP AQ 02, 03)

Supplemental Form for Survey of Noise Potential

W213528

Transmittal Number

1191617

Facility

E. Manufacturer's Noise Profile on New Equipment

The applicant must attach the manufacturer's noise generation data for the equipment being proposed for installation. This data must specify the sound pressure levels for a complete 360° turn around the equipment, and at various distances from the equipment.

F. Plot Plan

The plot plan required in form BWP AQ CPA 01 and BWP AQ CPA 03 must include location of the noise source(s) and the distances from the source(s) to the property lines and the nearest inhabited residences, as well as indications of possible future construction areas.

G. Community Sound Level Criteria

Approval of the proposed new equipment or proposed corrective measures will not be granted if the installation:

1. Increases broadband sound level by more than 10dB (A).
2. Produces a "pure tone" condition – when any octave band center frequency sound pressure level exceeds the two adjacent center frequency sound pressure levels by 3 decibels or more.
3. Creates a potential condition of air pollution as defined in 310 CMR 7.01.

Note: These criteria are measured both at the property line and at the nearest inhabited residence. Ambient is defined as the background A-Weighted sound pressure level that is exceeded 90% of the time measured during equipment operating hours. The ambient may also be established by other means with the consent of the department.

H. Certification

The seal and signature of a Massachusetts Registered Professional Engineer must be entered below. This certifies that the information contained in this form has been checked for accuracy, and that the design represents good air pollution control engineering practice. (These must be originals. No photocopies, etc., of the seal and signature will be accepted.)

Stephen Piper

Print name

Authorized signature

Sr. Project Manager

Position/title


M. J. Bradley & Associates

Representing

Date

36039

P.E.#



5 BEST AVAILABLE CONTROL TECHNOLOGY ANALYSIS

Chelsea-Sandwich LLC requested a pre-application meeting with DEP NERO in order to obtain a preliminary indication on the approvability of the proposed RTO emission control device for control of residual oil tanks and truck loading at the Chelsea Terminal. At the pre-application meeting Ed Braczyk of DEP indicated that an RTO rated for 99% VOC destruction would be considered BACT.

Regarding the capture of emissions, it was explained that the emissions capture system for the residual oil tanks was rated for 95% and that the emissions capture system for the residual oil truck loading was rated 90% capture. Ed Braczyk acknowledged that the tank vents and the truck loading operations were not conducive to 100% capture. Due to the safety requirements associated with operation of a petroleum storage tank, the capture system cannot be tight fitting as there cannot be a risk of under pressurizing or over pressurizing the tanks (resulting in tank collapse and catastrophic spill). In the case of the truck loading, the capture system cannot interfere with the top loading nozzle or the operator's view of the liquid level in the truck.

Because the control of emissions from residual oil tanks and residual truck loading is not common to the bulk terminal industry, Ed Braczyk indicated that this Non-Major CPA application would not require a top-down discussion of all control alternatives. In summary, Ed concurred the use of a 90 to 95% capture system for vents on the residual oil tanks and residual oil truck loading and a RTO control system rated for 99% VOC destruction would be approvable as BACT.

In the event that the RTO is only receiving a fraction of emissions based on operational slowdowns, the ability to demonstrate 99% reduction could be limited by the sensitivity of the test method. Based on the projected potential VOC emissions going to the RTO from the residual oil storage tanks and the residual oil truck loading, the RTO outlet hourly emission rate will not exceed 0.63 lb/hour.

6 RECORDKEEPING AND REPORTING PROCEDURES

To ensure compliance with the proposed limitations, Chelsea Sandwich LLC proposes to maintain records of the operation of the RTO by tracking (recording) the operating temperature of the unit as a means to demonstrate that the unit is meeting the 99% destruction efficiency guarantee. Monthly product throughput records will be maintained through receipt and sales data as a means to track compliance with the 12-month rolling annual emission limits. Because the product throughputs are directly related to the emissions, it will not be necessary to recalculate emissions every month. Emission inventory reports will be submitted to DEP as required in 310 CMR 7.12. The following provides a summary of the specific records and assumptions that will be maintained by Chelsea-Sandwich Terminal.

6.1 Combustion Emissions

For the RTO, the products of combustion emissions will be calculated based on vendor guaranteed emissions rates for NO_x of 3 ppm for CO of 50 ppm. Emissions of PM, CO and SO₂ for the RTO will be calculated based on AP-42 emission factors and the quantity of natural gas used as metered for billing purposes. See the calculation worksheet (see Appendix A).

For the boilers, the products of combustion emissions will be calculated based on AP-42 emission factors and the quantity of fuel fired. See the calculation worksheet (see Appendix A).

6.2 VOC Emissions

The VOC emissions (after control) will be well below the 50 tpy major source threshold. The calculation of facility-wide VOC emissions is provided in Appendix A and incorporates a combination of AP-42 emission factors and adjusted factors based on test results showing higher than AP-42 factors for residual oil truck loading and residual oil storage tanks. Chelsea Sandwich LLC will maintain a record of product throughputs to demonstrate that the 12-month rolling total is less than the product throughputs used to calculate potential VOC emissions and facility-wide emissions are therefore less than 50 tons.

APPENDIX A
EMISSION CALCULATIONS

Unit ID#	Unit Description	Rating	Fuel	VOC	NO _x	Potential Emissions (TPY)						
						SO ₂	CO	PM	PM10	PM2.5	NH3	
1 - 1	Boiler	12	MMBTU/hr	#6 Oil	0.396	19.272	27.506	1.752	2.738	1.685	0.626	0.280
1 - 2	Boiler	9.86	MMBTU/hr	#6 Oil	0.325	15.835	22.601	1.440	2.250	1.384	0.514	0.230
1 - 3	RTO			NG	0.017	0.848	0.236	8.601	0.024	0.024	0.024	n/a
Unit ID#	Unit Description		Material Processed									
2 - 2	Residual Truck Loading Rack		Residual (After Control)	3.535	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a
2 - 2	Distillate Truck Loading Rack		Distillates	6.870	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a
2 - 3	Barge Loading		Distillates/Residual	1.595	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a
Unit ID#	Unit Description	Storage Cap. (gal)	Current Contents									
4 - 101	AST Vertical Fixed	840,000	No. 2 Oil	0.77	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a
4 - 102	AST Vertical Fixed	840,000	No. 6 Oil	*	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a
4 - 103	AST Vertical Fixed	840,000	No. 6 Oil	*	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a
4 - 104	AST Vertical Fixed	840,000	No. 6 Oil	*	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a
4 - 105	AST Vertical Fixed	840,000	No. 2 Oil	0.77	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a
4 - 106	AST Vertical Fixed	840,000	No. 6 Oil	*	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a
4 - 107	AST Vertical Fixed	504,000	LSD	0.46	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a
4 - 108	AST Vertical Fixed	840,000	No. 2 Oil	0.77	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a
4 - 109	AST Vertical Fixed	840,000	LSD	0.77	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a
4 - 110	AST Horiz Fixed	30,000	Fuel Add	0.10	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a
4 - 111	AST Horiz Fixed	30,000	Fuel Add	0.51	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a
4 - 115	AST Horiz Fixed	30,000	Slop	0.08	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a
4 - 114	AST Horiz Fixed	4,000	Fuel Add	0.00	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a
4 - 116	AST Horiz Fixed	5,200	LSD	0.00	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a
4 - 117	AST Horiz Fixed	3,000	Fuel Add	0.00	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a
4 - 201	AST Vertical Fixed	4,200,000	No. 2 Oil	2.21	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a
4 - 202	AST Vertical Fixed	5,040,000	No. 6 Oil	*	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a
4 - 203	AST Vertical Fixed	3,150,000	No. 6 Oil	*	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a
4 - 204	AST Vertical Fixed	3,990,000	No. 6 Oil	*	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a
4 - 205	AST Vertical Fixed	5,040,000	No. 2 Oil	2.53	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a
4 - BH1	AST Horiz Fixed	1,000	No. 6 Oil	0.00	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a
4 - BH2	AST Horiz Fixed	1,000	No. 6 Oil	0.00	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a
*Total for 7 No. 6 Oil Tanks				15.40	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a
Total				37.105	35.955	50.343	11.792	5.012	3.093	1.164	0.511	

* These tanks are summarized above as Total for 7 No. 6 Oil Tanks.

Unit ID#	Unit Description	Potential Emissions (TPY)						Total Hap
		Benzene	Ethylbenzene	Isooctane	n-Hexane	Toluene	Xylene	
1 - 1	Boiler	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000
1 - 2	Boiler	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000
1 - 3	RTO	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000
<u>Unit ID#</u>	<u>Unit Description</u>							
2 - 2	Residual Truck Loading Rack After Control	0.2855	0.0301	0.0000	0.0213	0.1679	0.1010	0.6058
2 - 2	Distillate Truck Loading Rack	0.5339	0.0572	0.0000	0.0498	0.3170	0.1922	1.1501
2 - 3	Barge Loading Distillate/Residual	0.1243	0.0133	0.0000	0.0114	0.0737	0.0447	0.2674
<u>Unit ID#</u>	<u>Unit Description</u>							
4 - 101	Vertical Fixed	0.0016	0.0024	0.0000	0.0003	0.0181	0.0447	0.0672
4 - 102	Vertical Fixed	*	*	*	*	*	*	*
4 - 103	Vertical Fixed	*	*	*	*	*	*	*
4 - 104	Vertical Fixed	*	*	*	*	*	*	*
4 - 105	Vertical Fixed	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000
4 - 106	Vertical Fixed	*	*	*	*	*	*	*
4 - 107	Vertical Fixed	0.0010	0.0014	0.0000	0.0002	0.0108	0.0267	0.0401
4 - 108	Vertical Fixed	0.0016	0.0024	0.0000	0.0003	0.0181	0.0447	0.0672
4 - 109	Vertical Fixed	0.0016	0.0024	0.0000	0.0003	0.0181	0.0447	0.0672
4 - 110	Horiz Fixed	0.0002	0.0002	0.0000	0.0000	0.0018	0.0045	0.0068
4 - 111	Horiz Fixed	0.0008	0.0012	0.0000	0.0002	0.0092	0.0228	0.0343
4 - 115	Horiz Fixed	0.0002	0.0000	0.0000	0.0000	0.0001	0.0001	0.0003
4 - 114	Horiz Fixed	0.0000	0.0002	0.0000	0.0000	0.0018	0.0045	0.0067
4 - 116	Horiz Fixed	0.0000	0.0000	0.0000	0.0000	0.0001	0.0002	0.0002
4 - 117	Horiz Fixed	0.0000	0.0000	0.0000	0.0000	0.0000	0.0001	0.0001
4 - 201	Vertical Fixed	0.0046	0.0069	0.0000	0.0009	0.0518	0.1284	0.1927
4 - 202	Vertical Fixed	*	*	*	*	*	*	*
4 - 203	Vertical Fixed	*	*	*	*	*	*	*
4 - 204	Vertical Fixed	*	*	*	*	*	*	*
4 - 205	Vertical Fixed	0.0053	0.0079	0.0000	0.0011	0.0594	0.1471	0.2207
4 - BH1	Horiz Fixed	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000
4 - BH2	Horiz Fixed	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000
*Total for 7 No. 6 Oil Tanks		1.2400	0.1300	0.0000	0.0900	0.7300	0.7300	2.9200
Total		2.200	0.256	0.000	0.176	1.478	1.537	5.647

* These tanks are summarized above as Total for 7 No. 6 Oil Tanks

Chelsea Sandwich LLC
Chelsea, Massachusetts

ID#	101	102	103	104	105	106	107	108
Type	AST	AST	AST	AST	AST	AST	AST	AST
Type 2	Vertical Fixed	Vertical Fixed	Vertical Fixed	Vertical Fixed	Vertical Fixed	Vertical Fixed	Vertical Fixed	Vertical Fixed
diameter	60	60	60	60	60	60	48	60
height	40	40	40	40	40	40	36	40
const.	steel	steel	steel	steel	steel	steel	steel	steel
capacity	840,000	840,000	840,000	840,000	840,000	840,000	504,000	840,000
pot. turns	300.0	300.0	180.0	11.8	300.0	12.9	300.0	300.0
pot. thru	252,000,000	252,000,000	151,200,000	9,953,217	252,000,000	10,815,030	151,200,000	252,000,000
avg fill	20	20	20	20	20	20	18	20
shell lining	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a
roof color	Med. gray	Med. gray	Med. gray	Med. gray	Med. gray	Med. gray	Med. gray	Med. gray
cond.	good	good	good	good	good	good	good	good
shell color	Med. gray	Med. gray	Med. gray	Med. gray	Med. gray	Med. gray	Med. gray	Med. gray
cond.	good	good	good	good	good	good	good	good
roof type	cone	cone	cone	cone	cone	cone	cone	cone
deck type	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a
No. Columns	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a
cone ht.	2	2	2	2	2	2	2	2
dome rad.	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a
cone slope	0.0667	0.0667	0.0667	0.0667	0.0667	0.0667	0.0667	0.0667
V.V.	-0.03	-0.03	-0.03	-0.03	-0.03	-0.03	-0.03	-0.03
P.V.	0.03	0.03	0.03	0.03	0.03	0.03	0.03	0.03
pot. cont.	No. 2 Oil	No. 6 Oil	No. 6 Oil	No. 6 Oil	No. 2 Oil	No. 6 Oil	LSD	2 Oil
primary seal	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a
secondary seal	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a
deck type	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a
fittings	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a

Chelsea Sandwich LLC
Chelsea, Massachusetts

ID#	109	110	111	115	114	116	117	201
Type	AST	AST	AST	AST	AST	AST	AST	AST
Type 2	Vertical Fixed	Horiz Fixed	Horiz Fixed	Horiz Fixed	Horiz Fixed	Horiz Fixed	Horiz Fixed	Vertical Fixed
diameter	60	12	12	12	8	8	5	120
height	40	35	35	35	10	13	18	60
const.	steel	steel	steel	steel	steel	steel	steel	steel
capacity	840,000	30,000	30,000	30,000	4,000	5,200	3,000	4,200,000
pot. turns	300.0	1300.0	1300.0	1300.0	50.0	50.0	50.0	50.0
pot. thru	252,000,000	39,000,000	39,000,000	39,000,000	200,000	260,000	150,000	210,000,000
avg fill	20	18	18	18	5	7	9	30
shell lining	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a
roof color	Med. gray	Med. gray	Med. gray	Med. gray	Med. gray	Med. gray	Med. gray	Med. gray
cond.	good	good	good	good	good	good	good	good
shell color	Med. gray	Med. gray	Med. gray	Med. gray	Med. gray	Med. gray	Med. gray	Med. gray
cond.	good	good	good	good	good	good	good	good
roof type	cone	cone	cone	cone	cone	cone	cone	cone
deck type	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a
No. Columns	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a
cone ht.	2	0.5	0.5	n/a	n/a	n/a	n/a	4
dome rad.	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a
cone slope	0.0667	0.0833	0.0833	n/a	n/a	n/a	n/a	n/a
V.V.	-0.03	-0.03	-0.03	-0.03	-0.03	-0.03	-0.03	0.0667
P.V.	0.03	0.03	0.03	0.03	0.03	0.03	0.03	-0.03
pot. cont.	LSD	Fuel Add	Fuel Add	Slop	Fuel Add	LSD	Fuel Add	0.03
primary seal	n/a	n/a	n/a	n/a	n/a	n/a	n/a	No. 2 Oil
secondary seal	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a
deck type	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a
fittings	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a

Chelsea Sandwich LLC
Chelsea, Massachusetts

ID#	202	203	204	205	BH1	BH2
Type	AST	AST		AST		AST
Type 2	Vertical Fixed	Vertical Fixed	Vertical Fixed	Vertical Fixed	Horiz Fixed	Horiz Fixed
diameter	120	92	103	120	4	4
height	60	64	64	60	11	11
const.	steel	steel	steel	steel	steel	steel
capacity	5,040,000	3,150,000	3,990,000	5,040,000	1,000	1,000
pot. turns	12.4	9.9	15.7	50.0	400.0	400.0
pot. thru	62,635,483	31,221,666	62,452,930	252,000,000	400,000	400,000
avg fill	30	32	32	30	6	6
shell lining	n/a	n/a	n/a	n/a	n/a	n/a
roof color	Med. gray	Med. gray	Med. gray	Med. gray	Med. gray	Med. gray
cond.	good	good	good	good	good	good
shell color	Med. gray	Med. gray	Med. gray	Med. gray	Med. gray	Med. gray
cond.	good	good	good	good	good	good
roof type	cone	cone	cone	cone	cone	cone
deck type	n/a	n/a	n/a	n/a	n/a	n/a
No. Columns	n/a	n/a	n/a	n/a	n/a	n/a
cone ht.	4	3	3.5	4	n/a	n/a
dome rad.	n/a	n/a	n/a	n/a	n/a	n/a
cone slope	0.0667	0.06522	0.06796	0.0667	n/a	n/a
V.V.	-0.03	-0.03	-0.03	-0.03	-0.03	-0.03
P.V.	0.03	0.03	0.03	0.03	0.03	0.03
pot. cont.	No. 6 Oil	No. 6 Oil	No. 6 Oil	No. 2 Oil	No. 6 Oil	No. 6 Oil
primary seal	n/a	n/a	n/a	n/a	n/a	n/a
secondary seal	n/a	n/a	n/a	n/a	n/a	n/a
deck type	n/a	n/a	n/a	n/a	n/a	n/a
fittings	n/a	n/a	n/a	n/a	n/a	n/a

Chelsea Sandwich LLC
Process Calculation Sheet

Process ID#: 1-1

Boiler #1

12.000 MMBTU/hr

AP-42 Emission Factors*

#6 Oil combustion/Commercial

150,000 BTU/gal for #6 Oil 0.5% S

PM	7.82 lb/1000 gallon
CO	5.0 lb/1000 gallon
SO ₂	78.5 lb/1000 gallon
NO _x	55.0 lb/1000 gallon
VOC	1.130 lb/1000 gallon, non-methane
PM2.5	1.786 lb/1000 gallon
PM10	4.808 lb/1000 gallon
NH3	0.800 lb/1000 gallon**

Potential hours per year:

8,760

*Table 1.3-1 Criteria Pollutant Emission Factors for Fuel Oil Combustion and
Table 1-3.3 Emission Factors for Total Organic Compounds (9/98) and
Table 1.3-7 Cumulative Particle Size Distribution

**Provided by DEP 1/17/03

Calculations

Max lbs/hr = Total MMBTU/hr * emission factor / (150,000 BTU/gal * 1,000,000) / 1000

Potential TPY = Max lb/hr * potential hours / 2000 lb/ton

Criteria Pollutants	Pot lb/hr	Pot TPY
Particulate Matter	0.63	2.738
Carbon Monoxide	0.40	1.752
Sulfur Dioxide	6.28	27.506
Nitrogen Dioxide	4.40	19.272
Volatile Organic Compounds	0.09	0.396
Particulate Matter 2.5	0.14	0.626
Particulate Matter 10	0.38	1.685
Ammonia	0.06	0.280

Chelsea Sandwich LLC
Process Calculation Sheet

Process ID#: 1-2

Boiler #2

9.860 MMBTU/hr

AP-42 Emission Factors

#6 Oil combustion/Commercial

150,000 BTU/gal for #6 Oil 0.5% S

PM	7.82 lb/1000 gallon
CO	5.0 lb/1000 gallon
SO ₂	78.5 lb/1000 gallon
NO _x	55.0 lb/1000 gallon
VOC	1.130 lb/1000 gallon, non-methane
PM2.5	1.786 lb/1000 gallon
PM10	4.808 lb/1000 gallon
NH3	0.800 lb/1000 gallon**

Potential hours per year: 8,760

*Table 1.3-1 Criteria Pollutant Emission Factors for Fuel Oil Combustion and
Table 1-3.3 Emission Factors for Total Organic Compounds (9/98)
Table 1.3-7 Cumulative Particle Size Distribution

**Provided by DEP 1/17/03

Calculations

Max lbs/hr = Total MMBTU/hr * emission factor / (150,000 BTU/gal * 1,000,000) / 1000

Potential TPY = Max lb/hr * potential hours / 2000 lb/ton

Criteria Pollutants	Pot lb/hr	Pot TPY
Particulate Matter	0.51	2.250
Carbon Monoxide	0.33	1.440
Sulfur Dioxide	5.16	22.601
Nitrogen Dioxide	3.62	15.835
Volatile Organic Compounds	0.07	0.325
Particulate Matter 2.5	0.12	0.514
Particulate Matter 10	0.32	1.384
Ammonia	0.05	0.230

Chelsea Sandwich LLC
Process Calculation Sheet

Organic Liquid (<1.5 psi) Barge Loading

Emission factor	Distillate Throughput	Potential gal/yr
0.0130 lb/10 ³ gal *	Kerosene	10,000,000
0.0120 lb/10 ³ gal *	Distillates	60,000,000
0.03900 lb/10 ³ gal ^	Residual Oil	60,000,000

* AP-42 5.2-6 Total Organic Emission Factors
for Petroleum Marine Vessel Sources (1/95)

^ Reflects 433 times the AP-42 factor of .00009 lb/10³ gal based on testing at the Truck Rack

Max lbs/hr = Total gallons/hr * potential emission factor

Potential TPY = Max lb/hr * potential hours / 2000 lb/ton

8,760 Potential Hours/year

Kero 0.065 Pot Tpy

NMVOC

1.595 Pot Tpy

Dist 0.360 Pot Tpy

Res 1.170 Pot Tpy

HAP Vapor Weight Percents

	Distillate/Residual*	Kerosene
Benzene	8.06%	1.46%
Toluene	4.74%	1.85%
Ethylbenzene	0.85%	0.44%
Xylene	2.85%	1.66%
Hexane	0.60%	3.45%
Isooctane	0.00%	0.00%
MTBE	0.00%	0.00%

* Distillate factors are used for worst case scenario.

HAPs	Distillate Pot TPY	Kerosene Pot TPY	Residual Pot TPY	Total Pot TPY
Benzene	0.029	0.0009	0.09430	0.1243
Toluene	0.017	0.0012	0.05546	0.0737
Ethylbenzene	0.003	0.0003	0.00995	0.0133
Xylene	0.010	0.0011	0.03335	0.0447
Hexane	0.002	0.0022	0.00702	0.0114
Isooctane	0.000	0.0000	0.00000	0.0000
MTBE	0.000	0.0000	0.00000	0.0000

Criteria Pollutants	lb/hr	Pot TPY
Particulate Matter	0.000	0.000
Sulfur Dioxide	0.000	0.000
Nitrogen Dioxide	0.000	0.000
Carbon Monoxide	0.000	0.000
Volatile Organic Compounds	0.364	1.595

Chelsea Sandwich LLC
Process Calculation Sheet

Process ID#: 2-2

Organic Liquid (<1.5 psi) Tank Truck Loading

<u>Emission factor</u>	<u>Distillate Throughput</u>	<u>Potential gal/vr</u>	<u>Potential gal/hr</u>
0.0400 lb/10 ³ gal*	Kerosene	15,000,000	1,712
0.0300 lb/10 ³ gal*	Distillates	438,000,000	50,000
0.0142 lb/10 ³ gal (calculated after control)	Residual Oil	500,000,000	57,078

* AP-42 5.2-5 Total Uncontrolled Organic Emission Factors
for Petroleum Liquid Rail Tank Cars and Tank Trucks (1/95)

8,760 Potential Hours/year (Distillate and Kerosene)

Max lbs/hr = Total gallons/hr * potential emission factor

Potential TPY (Distillate and Kero) = Max lb/hr * potential hours / 2000 lb/ton

Potential TPY (Residual) = Emission Factor (ppm) * exhaust rate (cfm) * 60 min/hour * hours/year * lb mole/cubic feet * lbs/lb mole / 2000lb/ton

Kero	0.068493151 Max lb/hr	34.002 Max lb/hr
	0.300 Pot Tpy	10.405 Pot Tpy
Dist	1.5 Max lb/hr	
	6.570 Pot Tpy	
Res	32.43 Pot Tpy uncontrolled	
	3.54 Pot Tpy controlled	

NMVOC

Residual Oil Calculation

16,667 Potential Hours/year (Residual Oil)
2,000 ppm
300 cfm
407 cubic feet/lb mole
44 lbs/ lb mole

HAP Vapor Weight Percents¹

	<u>Distillate / Residual*</u>	<u>Kerosene</u>
Benzene	8.06%	1.46%
Toluene	4.74%	1.85%
Ethylbenzene	0.85%	0.44%
Xylene	2.85%	1.66%
Hexane	0.60%	3.45%
Isooctane	0.00%	0.00%
MTBE	0.00%	0.00%

* Distillate factors are used for worst case scenario.

<u>HAPs</u>	<u>Distillate Pot TPY</u>	<u>Kerosene Pot TPY</u>	<u>Residual Pot TPY</u>	<u>Total Pot TPY</u>
Benzene	0.530	0.0044	0.2855	0.8194
Toluene	0.311	0.0056	0.1679	0.4849
Ethylbenzene	0.056	0.0013	0.0301	0.0873
Xylene	0.187	0.0050	0.1010	0.2932
Hexane	0.039	0.0104	0.0213	0.0710
Isooctane	0.000	0.0000	0.0000	0.0000
MTBE	0.000	0.0000	0.0000	0.0000

<u>Criteria Pollutants</u>	<u>lb/hr</u>	<u>Pot TPY</u>
Particulate Matter	0.000	0.000
Sulfur Dioxide	0.000	0.000
Nitrogen Dioxide	0.000	0.000
Carbon Monoxide	0.000	0.000
Volatile Organic Compounds	34.00	10.41

Chelsea Sandwich LLC
Process Calculation Sheet

Process ID#: 1-3		Cubic Feet per minute	9,000
RTO Combustion Emissions		Million Cubic Feet per year	6.3
Vendor Emission Factors		Lbs per Lb Mole - NO _x	46
Natural Gas combustion		Lbs per Lb Mole - SO ₂	64
PM	7.60 lbs/10 ⁶ scf	Lbs per Lb Mole - CO	28
CO	50.0 ppm		
SO ₂	0.6 ppm	Cubic Feet per Lb Mole	385
NO _x	3.0 ppm	Pounds per ton	2,000
VOC	5.50 lbs/10 ⁶ scf	Potential hours per year:	8,760
PM2.5	Same as PM	Minutes per Hour	60
PM10	Same as PM		

Calculations

Potential TPY = Emission Factor (ppm) * cubic feet/minute * 60 min/hour * hrs/year * lb mole/cubic feet * lbs/lb mole / 2000 lbs/ton

Potential TPY = Emission Factor (lbs/10⁶ scf) * Million Cubic Feet/year / 2000 lbs/ton

Criteria Pollutants	Pot lb/hr	Pot TPY
Particulate Matter	0.005	0.024
Carbon Monoxide	1.964	8.60
Sulfur Dioxide	34.442	0.24
Nitrogen Dioxide	0.194	0.85
Volatile Organic Compounds	0.004	0.017
Particulate Matter 2.5	0.005	0.024
Particulate Matter 10	0.005	0.024

Chelsea Sandwich LLC
Chelsea, Massachusetts
Tank Summary

Tank Number	Tank Contents	Tank Capacity (Gallons)	Potential Tank Throughput (Gallons)	Total VOC
101	No. 2 Oil	840,000	252,000,000	0.77
105	No. 2 Oil	840,000	252,000,000	0.77
107	LSD	504,000	151,200,000	0.46
108	No. 2 Oil	840,000	252,000,000	0.77
109	LSD	840,000	252,000,000	0.77
110	Fuel Add	30,000	39,000,000	0.10
111	Fuel Add	30,000	39,000,000	0.51
115	Slop	30,000	39,000,000	0.08
114	Fuel Add	4,000	200,000	0.00
116	LSD	5,200	260,000	0.00
117	Fuel Add	3,000	150,000	0.00
201	No. 2 Oil	4,200,000	210,000,000	2.21
205	No. 2 Oil	5,040,000	252,000,000	2.53
102	No. 6 Oil	840,000	12,508,929	15.40 See Attached Calculation
103	No. 6 Oil	840,000	9,799,806	
104	No. 6 Oil	840,000	9,953,217	
106	No. 6 Oil	840,000	10,815,030	
202	No. 6 Oil	5,040,000	62,635,483	
203	No. 6 Oil	3,150,000	31,221,666	
204	No. 6 Oil	3,990,000	62,452,930	
BH1	No. 6 Oil	1,000	400,000	0.00
BH2	No. 6 Oil	1,000	400,000	0.00
Total Emissions				24.37

Chelsea Sandwich LLC
Residual Oil Calculation Sheet

Factors		
Potential Inlet concentration	2000	ppm
Exhaust Flow rate	4300	scfm
Hours per year	8760	
Cubic feet per pound mole	385	
Pound per pound mole	44	
Pounds per ton	2000	

Potential TPY Calculation

Potential Tons per Year = 2,000 cubic feet/1000000 cubic feet * 4,300 cubic feet/minute * 60 min/hour * 8760 hours/year * 1 lb mole/385 cubic feet * 44 lbs/lb mole * 1 ton/2,000lbs

Potential	258 tpy
-----------	---------

Control Factors	
Capture Efficiency	95%
VOC destruction efficiency	99%

Controlled Potential TPY Calculation

Controlled Tons per year = (potential tpy * .05)+((potential tpy*.95)*.01)

With Control Strategy	15.4 tpy
-----------------------	----------

Chelsea Sandwich LLC
Chelsea, MA
HAP Emissions Summary (Pounds)

Losses (lbs.)						
Tank ID	Benzene	Ethylbenzene	Isooctane	n-Hexane	Toluene	Xylene
101	3.20	4.82		0.66	36.13	89.49
105	0.00	0.00	0.00	0.00	0.00	0.00
107	1.91	2.88	0.00	0.39	21.57	53.44
108	3.20	4.82	0.00	0.66	36.13	89.49
109	3.20	4.82	0.00	0.66	36.13	89.49
110	0.32	0.49	0.00	0.07	3.66	9.08
111	1.63	2.46	0.00	0.33	18.44	45.69
114	0.01	0.01	0.00	0.00	0.10	0.24
115	0.32	0.49	0.00	0.07	3.66	9.08
116	0.01	0.02	0.00	0.00	0.13	0.31
117	0.01	0.01	0.00	0.00	0.07	0.18
201	9.18	13.83	0.00	1.88	103.69	256.86
205	10.51	15.84		2.15	118.74	294.17
102	1.24	0.13	0.00	0.09	0.73	0.73
103						
104						
106						
202						
203						
204						
BH1	0.00	0.00	0.00	0.00	0.00	0.00
BH2	0.00	0.00	0.00	0.00	0.00	0.00

No. 6 Oil Tanks



M. J. Bradley & Associates
1000 Elm Street
Second floor
Manchester, NH 03101
Tel: 603-647-5746
Fax: 603-647-0929

MEMO

TO: Tom Keefe
FROM: Steve Piper
Cc: Ron Kenny
DATE: April 1, 2008
RE: Chelsea Terminal Rack Exhaust Testing

On March 7, 2008, myself and Paul Murphy collected air samples from the residual oil loading operations as a means to better characterize the rack contribution to the overall VOC emissions ducted to the existing odor control device. During previous testing efforts sampling focused on the combined exhaust of the residual oil storage tanks and the residual oil rack loading lanes as well as sampling of individual tank within the tank farm. During pre-permit application meetings with the MADEP, they expressed interest in knowing how the actual residual oil loading rack emissions compared with EPA-published emission factors (AP-42).

The test plan was to collect a total of six bag samples; three from the headspace of trucks during residual loading (splash loading), and a corresponding three samples from the flex hose collecting the displaced vapors from the residual oil loading. The bag samples were then taken to a nearby lab for analysis using Method 25A (calibrated to propane). Results of the sample analyses are summarized below.

Residual Oil Type	Truck Headspace (ppm)	Vapor Collection Duct (ppm)
2.2%	2,860	1,120
1.0%	6,100	1,900
0.5%	4,350	4,700*
AVG	4,437	1,510

Handwritten note: 2,000

*Sample disregarded, suspect that the sampling tube was contaminated with oil residue.

The average headspace concentration in the trucks of 4,437 ppm was slightly higher than the average headspace concentrations in the residual oil storage tanks of 3,547 ppm (a lot more samples collected). The difference seems rationale given that the truck were testing during an active top loading event whereas the majority of tank samples were collected during periods of no activity.

An attempt was made to measure the actual flow in each vapor collection duct. The purpose was to confirm the design exhaust rate of 300 cfm per loading lane and to

provide for and ability to calculate the capture efficiency. However, the pitot tube repeatedly became clogged by the tar buildup on the inside of the flex hose during each attempt to measure flow.

To calculate potential emissions from the residual loading rack lanes, we used the residual oil throughput limitation of 500,000,000 gallons/year (from Ron Kenny) and the loading pump rate of 500 gallons/minute to calculate that the loading could operate 16,667 hours/year (for one lane or less hours for multiple lanes). To convert from VOC concentration (ppm) to annual quantity of VOC emissions, the design exhaust rate of 300 cfm and the ideal gas law for a 100 °F air stream was used. For the purpose of "potential" emission calculation, a concentration of 2,000 ppm was used (5% higher than highest test result and consistent with concentrations measured at the control system inlet. Based on the 2,000 ppm potential concentration, the potential uncontrolled VOC emissions (as propane) from truck loading of residual oil would be 32.4 tpy.

$$\frac{2,000 \text{ ft}^3}{10^6 \text{ ft}^3} * \frac{300 \text{ ft}^3}{\text{min}} * \frac{60 \text{ min}}{\text{hour}} * \frac{16,667 \text{ hr}}{\text{year}} * \frac{\text{lb mole}}{407 \text{ ft}^3} * \frac{44 \text{ lb}}{\text{lb mole}} * \frac{1 \text{ ton}}{2,000 \text{ lb}} = 32.4 \text{ tpy}$$

Back-calculating the uncontrolled emission factor would indicate that the residual oil truck loading operation emits 0.13 lb/10³ gallons loaded. The current emission factor published by EPA (AP-42) in 0.0003 lb/10³ gallons loaded.

Based on the emission control strategy being proposed of 90% capture efficiency and 99% VOC destruction efficiency of the captures vapors, the controlled potential emissions would be 3.5 tpy from residual truck loading.

$$\left[\frac{0.13 \text{ lb}}{10^3 \text{ gal}} (1 - 0.9 \text{ capture}) \right] + \left[\frac{0.13 \text{ lb}}{10^3 \text{ gal}} (0.9) (1 - 0.99 \text{ control}) \right]$$


$$0.013$$

+

$$0.0012$$

$$\text{After Control} = 0.014 \frac{\text{lb}}{10^3 \text{ gal}}$$

$$\boxed{\text{calc page says } 0.0142 \frac{\text{lb}}{10^3 \text{ gal}}}$$



M. J. Bradley & Associates
1000 Elm Street
Second floor
Manchester, NH 03101
Tel: 603-647-5746
Fax: 603-647-0929

MEMO

TO: Tom Keefe
FROM: Steve Piper
Cc: Ron Kenny
DATE: April 2, 2008
RE: Chelsea Terminal Residual Tank Vent Testing

On several occasions from September thru November 2007 air sampling and testing was conducted to characterize emissions from the residual oil storage tanks as a means to understand why the bed life of the odor control device (dry scrubber) was shorter than anticipated. During the control inlet testing efforts there was little or no activity with residual oil truck loading. As such, the emission measured reflected only working and breathing losses for the residual oil storage tanks.

Initial testing involved the collection of bag samples from the headspace of residual oil tanks and corresponding samples at the inlet of the odor control system. The bag samples were then taken to a nearby lab for analysis using Method 25A (calibrated to propane). Results of the sample analyses are summarized below.

Date	Tank Headspace* (ppm)	Emission Control Inlet (ppm)
Sept 19, 2007	5,700	1,660
Sept 26, 2007	3,900	1,400
Oct 15, 2007	2,750	825
Oct 18, 2007	4,595	802
Oct 22, 2007	2,910	-
Oct 29, 2007	2,990	670
Nov 5, 2007	3,660	820
Nov 28, 2007	2,145	632
AVG	3,456	973
Range	638 - 8,100	632-1,670

Assn 2,000

*Average of results from multiple tanks.

The average headspace concentration in the residual oil tanks of 3,456 ppm was slightly lower than the average headspace concentrations in the residual oil trucks during loading of 4,437 ppm. The difference seems rationale given that the truck were testing during an active top loading event whereas the majority of tank samples were collected during

periods with a range of conditions from empty with the heat off to active loading and air sparging at high temperatures.

The flow rate at the odor control inlet was measured on a few occasions with results ranging from 4,300 to 4,900 SCFM. To calculate potential emissions from the residual storage tanks, we used the flow rate of 4,300 SCFM and a maximum potential inlet concentration of 2,000 ppm (as propane). To convert from VOC concentration (ppm) to annual quantity of VOC emissions the ideal gas law for a standard air temperature was used. The worst case concentration of 2,000 ppm was reflects a 20% safety factor from the highest actual inlet concentration measured of 1,670 ppm and is consistent the concentration from the residual truck loading operation also going to the odor control system. Based on the 2,000 ppm potential concentration, the potential uncontrolled VOC emissions (as propane) from working and breathing losses from the residual oil storage tanks would be 258 tpy.

$$\frac{2,000 \text{ ft}^3}{10^6 \text{ ft}^3} * \frac{4,300 \text{ ft}^3}{\text{min}} * \frac{60 \text{ min}}{\text{hour}} * \frac{8,760 \text{ hr}}{\text{year}} * \frac{\text{lb mole}}{385 \text{ ft}^3} * \frac{44 \text{ lb}}{\text{lb mole}} * \frac{1 \text{ ton}}{2,000 \text{ lb}} = 258 \text{ tpy}$$

Calculating the residual oil tank working and breathing emissions using the traditional TANKS model published by EPA indicated that the potential VOC emissions from the seven heated tanks at Chelsea Terminal would only be 1.0 tpy.

Based on the emission control strategy being proposed of 95% capture efficiency and 99% VOC destruction efficiency of the captures vapors, the controlled potential emissions would be 15.4 tpy from residual oil tanks.

TANKS 4.0.9d
Emissions Report - Detail Format
Total Emissions Summaries - All Tanks in Report

Emissions Report for: Annual

Tank Identification			Losses (lbs)
Tank 101	Chelsea Terminal Ltd.	Vertical Fixed Roof Tank	1,537.08
Tank 105	Chelsea Terminal Ltd.	Vertical Fixed Roof Tank	1,537.08
Tank 107	Chelsea Terminal Ltd.	Vertical Fixed Roof Tank	917.94
Tank 108	Chelsea Terminal Ltd.	Vertical Fixed Roof Tank	1,537.08
Tank 109	Chelsea Terminal Ltd.	Vertical Fixed Roof Tank	1,537.08
Tank 110	Chelsea Sandwich LLC	Horizontal Tank	203.99
Tank 111	Chelsea Sandwich LLC	Horizontal Tank	1,026.64
Tank 114	Chelsea Terminal, Ltd.	Horizontal Tank	5.43
Tank 115	Chelsea Sandwich LLC	Horizontal Tank	155.91
Tank 116	Chelsea Terminal, Ltd.	Horizontal Tank	5.40
Tank 117	Chelsea Sandwich LLC	Horizontal Tank	4.01
Tank 201	Chelsea Terminal Ltd.	Vertical Fixed Roof Tank	4,411.72
Tank 205	Chelsea Terminal Ltd.	Vertical Fixed Roof Tank	5,052.44
Tank BH1	Chelsea Terminal, Ltd.	Horizontal Tank	0.09
Tank BH2	Chelsea Terminal, Ltd.	Horizontal Tank	0.09
Total Emissions for all Tanks:			17,931.97

APPENDIX B

STANDARD MAINTENANCE AND OPERATING PROCEDURES



March 3, 2008

Global Petroleum
Chelsea Sandwich Terminal
Chelsea, MA

Regenerative Thermal Oxidation System Supplemental Information

RTO Operating Controls

1. Operating and Safety Controls

The RTO system uses a natural gas burner system with a dedicated combustion air blower to provide the initial reaction zone warm up. This occurs for approximately 1 hour. During this time the fume collection fan is off and vapors are not collected and delivered to the RTO system.

After the initial warm-up cycle is complete, the start-up burner is shut down and the fume collection fan is started. Collected vapors are drawn from the tank farm and the truck loading stations and delivered to the RTO system.

Multiple thermocouples monitor temperatures throughout the RTO. If the inlet fume stream does not contain adequate fuel value to maintain the reaction temperature, supplemental natural gas is injected to compensate. This supplemental fuel gas is introduced at the fume fan inlet to encourage mixing with the fume stream. The fuel gas is modulated to maintain the reaction zone minimum temperature of 1500 F, adding supplemental fuel to approximately 3% of the LEL at the inlet of the ceramic beds.

Every 3-5 minutes, the PLC system will reverse the flow through the ceramic heat exchange beds in order to maintain optimum temperature profiles for preheating the stream and for recovering the heat of reaction prior to discharging the stream to atmosphere. The natural gas feed is shut off before initiating the reverse flow through a position change in the air actuated poppet valves. Once the flow direction has been reversed, the natural gas feed is turned back on.

The fume fan is complete with a VFD system, which can be adjusted manually to optimize the capture volume and to account for seasonal operation changes at the terminal.